

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON SW 1/4 SW 1/4 NW 1/4 20 T 28 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 MILE NORTH, 1 EAST & 1/2 NORTH OF JOHNSON

2 WATER WELL OWNER: MARTIN, BLAKE
 RR#, St. Address, Box #: PO BOX 920 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : JOHNSON, KS 67855-0920 Application Number: 7,673

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 632 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 330 ft. below land surface measured on mo/day/yr 05/06/98
 Pump test data: Well water was 479 ft. after 4 hours pumping 250 gpm

Estimated Yield 250 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 632 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 632 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 340 ft. to 380 ft., From 0 ft. to 0 ft.
 From 467 ft. to 627 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 410 ft., From 0 ft. to 0 ft.
 From 410 ft. to 632 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 233

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	60	04 SANDY CLAY 31 CALICHE 05 SAND			
60	83	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
83	95	01 CLAY 20 LIMESTONE			
95	145	05 SAND 01 CLAY			
145	155	04 SANDY CLAY 05 SAND			
155	163	01 CLAY 20 LIMESTONE			
163	175	05 SAND 01 CLAY 11 GRAVEL			
175	181	01 CLAY 20 LIMESTONE			
181	220	05 SAND 01 CLAY 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/01/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/09/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 094 STANTON SW 1/4 SW 1/4 NW 1/4 20 T 28 S R 40 W

2 WATER WELL OWNER: MARTIN, BLAKE

RR#, St. Address, Box # : PO BOX 920

Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67855-0920

Application Number: 7,673

FROM	TO	LITHOLOGIC LOG
220	230	01 CLAY
230	345	05 SAND 11 GRAVEL 01 CLAY
345	356	09 COARSE SAND 11 GRAVEL
356	362	04 SANDY CLAY 20 LIMESTONE
362	370	31 CALICHE 20 LIMESTONE
370	395	19 SHALE 20 LIMESTONE
395	463	19 SHALE 23 SANDSTONE
463	478	19 SHALE 23 SANDSTONE 20 LIMESTONE
478	500	23 SANDSTONE 31 CALICHE
500	510	19 SHALE
510	546	31 CALICHE 23 SANDSTONE
546	580	31 CALICHE 23 SANDSTONE 19 SHALE
580	600	23 SANDSTONE 31 CALICHE
600	627	31 CALICHE 23 SANDSTONE 19 SHALE
627	640	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/01/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/09/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richman*