

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON SW 1/4 SW 1/4 SE 1/4 21 T 28 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 MILES EAST, 1 NORTH & 1/2 EAST OF JOHNSON

2 WATER WELL OWNER: CAILLOUET, DON
 RR#, St. Address, Box #: BOX 86 Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 245 ft. below land surface measured on mo/day/yr 03/27/98
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 394 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 394 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 334 ft. to 394 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 394 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	30	01 CLAY			
30	45	05 SAND 11 GRAVEL			
45	55	04 SANDY CLAY			
55	67	05 SAND 11 GRAVEL			
67	100	04 SANDY CLAY 20 LIMESTONE			
100	173	05 SAND 11 GRAVEL 28 ROCK			
173	203	04 SANDY CLAY 05 SAND			
203	220	05 SAND 04 SANDY CLAY			
220	264	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/28/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/06/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 094 STANTON	SE 1/4 SW 1/4 SE 1/4	21	T 28 S	R 40 W

2 WATER WELL OWNER: CAILLOUET, DON

RR#, St. Address, Box #: BOX 86

Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67855-

Application Number:

FROM	TO	LITHOLOGIC LOG
264	298	04 SANDY CLAY 05 SAND
298	338	05 SAND 11 GRAVEL
338	342	01 CLAY
342	363	05 SAND 28 ROCK 01 CLAY
363	378	05 SAND 11 GRAVEL 01 CLAY
378	401	05 SAND 28 ROCK
401	404	01 CLAY
404	412	01 CLAY 23 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/28/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/06/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*