

1 LOCATION OF WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON NE 1/4 SE 1/4 SW 1/4 30 T 28 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/2 MILE EAST & 1/4 MILE NORTH OF JOHNSON

2 WATER WELL OWNER: STANTON COUNTY GOLF CRSE Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: PO BOX 190
 City, State, ZIP code: JOHNSON, KS 67855-0190 Application Number: 30,805

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 633 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 332 ft. below land surface measured on mo/day/yr 04/27/98
 Pump test data: Well water was 390 ft. after 4 hours pumping 1140 gpm
 Estimated Yield 1140 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 633 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 633 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 360 ft. to 430 ft., From 0 ft. to 0 ft.
 From 480 ft. to 630 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 440 ft., From 0 ft. to 0 ft.
 From 440 ft. to 633 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	04 SANDY CLAY 05 SAND			
25	44	04 SANDY CLAY 31 CALICHE 05 SAND			
44	54	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
54	60	04 SANDY CLAY 01 CLAY			
60	81	01 CLAY 20 Limestone			
81	110	05 SAND 01 CLAY			
110	160	05 SAND 11 GRAVEL			
160	307	05 SAND 11 GRAVEL 28 ROCK			
307	369	28 ROCK			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/24/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/05/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 094 STANTON : NE 1/4 SE 1/4 SW 1/4 : 30 : T 28 S : R 40 W

2 WATER WELL OWNER: STANTON COUNTY GOLF CRSE
 RR#, St. Address, Box #: PO BOX 190 Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67835-0190 Application Number: 30,805

FROM	TO	LITHOLOGIC LOG
369	393	04 SANDY CLAY 05 SAND
393	401	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
401	406	04 SANDY CLAY
406	419	05 SAND 01 CLAY
419	430	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
430	435	31 CALICHE
435	436	20 LIMESTONE
436	465	19 SHALE 23 SANDSTONE
465	500	31 CALICHE 23 SANDSTONE
500	508	01 CLAY
508	525	31 CALICHE 23 SANDSTONE
525	531	31 CALICHE 19 SHALE
531	545	23 SANDSTONE 31 CALICHE
545	551	31 CALICHE 19 SHALE 23 SANDSTONE
551	577	23 SANDSTONE 31 CALICHE
577	581	20 LIMESTONE
581	603	23 SANDSTONE 31 CALICHE 20 LIMESTONE
603	621	23 SANDSTONE 31 CALICHE
621	630	31 CALICHE 23 SANDSTONE
630	640	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/24/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/05/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richman*