

professionals

MINTER-WILSON DRILLING CO.

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

INCORPORATED

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Leoti Speck
Stanton County
5-21-86

Location: SW $\frac{1}{4}$ 32-28-40
From Johnson - 1 Mile East, 3/4 Mile
South & 200' Northeast of old well

Static Water Level - 270

Test #1

- 0 6 Top soil
- 6 23 Brown clay
- 23 26 Fine sand
- 26 68 Brown clay
- 68 73 Fine sand
- 73 81 Brown clay
- 81 166 Fine medium sand - loose
- 166 186 Brown sandy clay
- 186 230 Fine to medium sand & gravel - loose
- 230 274 Fine sand - tight
- 274 281 Brown yellow clay
- 281 301 Blue clay
- 301 322 Fine, fine sand - small clay streak - mixed
- 322 337 Brown sandy clay
- 337 359 Fine to medium sand & gravel
- 359 372 Brown sandy clay
- 372 391 Fine to medium sand & gravel
- 391 405 Brown sandy clay
- 405 486 Brown sandy clay - white rock mixed - hard strip
- 486 490 Brown red yellow clay - Lost circulation at 500'
- 490 500 Yellow clay - 15% sand stone
- 500 530 Brown yellow red clay - hard pull down

ssionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269

P.O. Box A

GARDEN CITY, KANSAS 67846

Leoti Speck
Stanton County
5-22-86

Location: SW $\frac{1}{4}$ 32-28-40
From Johnson - 1 Mile East, 3/4 Mile
South & 300' east of old well

Static Water Level - 270

Test #2

0	3	Top soil
3	27	Brown clay
27	36	Fine sand
36	63	Brown clay
63	110	Fine to medium sand & gravel - loose
110	155	Fine to medium sand - loose
155	168	Fine to medium sand & gravel - loose
168	184	Brown sandy clay
184	199	Fine to medium sand & gravel - loose
199	215	Fine sand
215	258	Fine to medium sand & gravel - loose
258	277	Brown yellow clay
277	314	Blue clay
314	320	Fine sand
320	328	Brown clay
328	349	Fine to medium sand & gravel - loose
349	355	Brown sandy clay
355	380	Fine to medium sand & gravel - loose
380	412	Brown sandy clay
412	453	Brown sandy clay - white rock mixed
453	484	Brown clay - 20% sand stone
484	489	Brown red yellow clay - hard
489	530	Brown yellow clay - hard