

| | | | | |
|---------------------------|-----------------------------|----------------|-----------------|------------------|
| 1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
| County: STANTON | SE 1/4 SE 1/4 NW 1/4 | 26 | T 28 S | R 41W E/W |

Distance and direction from nearest town or city street address of well if located within city?

1/2 MILE NORTHWEST JOHNSON, KS2 WATER WELL OWNER: **HUBER J M CORP.**RR#, St. Address, Box # : **7120 I-40 WEST STE, 100**City, State, ZIP Code : **AMARILLO TX 79106**# **26-2 NAIRN**

Board of Agriculture, Division of Water Resources

Application Number: **950165**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: **460** ft. ELEVATION:Depth(s) Groundwater Encountered 1. **272** ft. 2. ft. 3. ft.WELL'S STATIC WATER LEVEL **272** ft. below land surface measured on mo/day/yr **5-17-95**Pump test data: Well water was **292** ft. after **1** hours pumping **120** gpmEst. Yield **120** gpm: Well water was ft. after hours pumping gpmBore Hole Diameter **11** in. to **460** ft., and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No **X**; If yes, mo/day/yr sample was submittedWater Well Disinfected? Yes **X** No

5 TYPE OF BLANK CASING USED:

1 Steel 3 RMP (SR)

2 PVC 4 ABS

5 Wrought iron

6 Asbestos-Cement

7 Fiberglass

8 Concrete tile

9 Other (specify below)

CASING JOINTS: Glued **X** Clamped

Welded

Threaded

Blank casing diameter **6** in. to **460** ft., Dia in. to ft., Dia in. to ft.Casing height above land surface **24** in., weight **2.902** lbs./ft. Wall thickness or gauge No. **280 SDR 21**

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel 3 Stainless steel

2 Brass 4 Galvanized steel

5 Fiberglass

6 Concrete tile

7 PVC

8 RMP (SR)

9 ABS

10 Asbestos-cement

11 Other (specify)

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot

3 Mill slot

2 Louvered shutter

4 Key punched

5 Gauzed wrapped

6 Wire wrapped

7 Torch cut

8 Saw cut

9 Drilled holes

10 Other (specify)

11 None (open hole)

SCREEN-PERFORATED INTERVALS: From **360** ft. to **460** ft., From ft. to ft.

From ft. to ft., From ft. to ft.

GRAVEL PACK INTERVALS: From **320** ft. to **460** ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL:

1 Neat cement

2 Cement grout

3 Bentonite

4 Other

HOLE PLUG

Grout Intervals: From **1** ft. to **20** ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank

4 Lateral lines

7 Pit privy

10 Livestock pens

11 Fuel storage

12 Fertilizer storage

13 Insecticide storage

14 Abandoned water well

15 Oil well/Gas well

16 Other (specify below)

2 Sewer lines

5 Cess pool

8 Sewage lagoon

9 Feedyard

3 Watertight sewer lines 6 Seepage pit

Direction from well?

North

How many feet?

3/8 mile

| FROM | TO | LITHOLOGIC LOG | FROM | TO | PLUGGING INTERVALS |
|------|-----|----------------------------|------|-----|-----------------------------|
| 0 | 1 | TOP SOIL | 387 | 396 | SANDY CLAY |
| 1 | 79 | SANDY CLAY & SAND | 396 | 404 | SAND & GRAVEL |
| 79 | 130 | SAND | 404 | 417 | YELLOW CLAY |
| 130 | 150 | CLAY & SAND STONE W/SAND | 417 | 433 | SAND & GRAVEL W/CLAY |
| 150 | 165 | SAND | 433 | 446 | SANDY CLAY W/SAND |
| 165 | 187 | SANDY CLAY W/SAND | 446 | 460 | BLACK & YELLOW CLAY W/SHALE |
| 187 | 195 | SAND | | | |
| 195 | 224 | SAND W/SANDY CLAY | | | |
| 224 | 237 | SAND W/SAND STONE | | | |
| 237 | 250 | SANDY CLAY | | | |
| 250 | 278 | SAND & GRAVEL W/SANDY CLAY | | | |
| 278 | 313 | YELLOW CLAY | | | |
| 313 | 337 | BLUE CLAY | | | |
| 337 | 353 | BLUE & YELLOW CLAY W/SAND | | | |
| 353 | 387 | SAND & GRAVEL | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **5-17-95** and this record is true to the best of my knowledge and belief. KansasWater Well Contractor's License No. **KWCL-430** This Water Well Record was completed on (mo/day/yr) **5-17-95**under the business name of **HOWARD DRUG CO. BOX 806 BEAVER, OK 73932** by (signature) *Howard Drug Co.*