

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON SE 1/4 SW 1/4 SE 1/4 19 T 28 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?

APPROX. 4 MILES WEST, 1 NORTH & 2/3 WEST OF JOHNSON

2 WATER WELL OWNER: NAIRN, ARCHIE

RR#, St. Address, Box #: PO BOX 486

Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67855-

Application Number: 1,986 & 5,340

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16
17	18	19	20
21	22	23	24
25	26	27	28
29	30	31	32

4 DEPTH OF COMPLETED WELL 378 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 235 ft. below land surface measured on mo/day/yr 09/23/97
 Pump test data: Well water was 275 ft. after 4 hours pumping 1150 gpm

Estimated Yield 1150 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 378 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 378 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .225

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 235 ft. to 375 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 330 ft., From 0 ft. to 0 ft.

From 330 ft. to 378 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHWEST

How many feet? 298

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	39	04 SANDY CLAY 31 CALICHE 05 SAND			
39	69	04 SANDY CLAY			
69	107	04 SANDY CLAY 05 SAND			
107	114	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
114	147	04 SANDY CLAY 20 LIMESTONE			
147	170	01 CLAY 05 SAND			
170	189	04 SANDY CLAY 05 SAND 20 LIMESTONE			
189	195	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
195	214	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/23/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/08/97 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 094 STANTON SE 1/4 SW 1/4 SE 1/4 19 T 28 S R 41 W

2 WATER WELL OWNER: NAIRN, ARCHIE
RR#, St. Address, Box #: PO BOX 486 Board of Agriculture, Division of Water Resources

City, State, ZIP code : JOHNSON, KS 67855- Application Number: 1,986 & 5,340

FROM	TO	LITHOLOGIC LOG
214	232	05 SAND 13 FINE GRAVEL
232	247	01 CLAY 05 SAND
247	290	05 SAND 13 FINE GRAVEL
290	301	04 SANDY CLAY
301	320	05 SAND 11 GRAVEL 01 CLAY
320	335	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
335	340	31 CALICHE 23 SANDSTONE
340	375	23 SANDSTONE 31 CALICHE
375	383	31 CALICHE
383	440	19 SHALE 20 Limestone

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/23/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/08/97 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichert*