

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: MORTON SE 1/4 SE 1/4 1/4 9 T 35 S R 43 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM ELKHART - 3 MILES WEST ON NORTH ROAD

2 WATER WELL OWNER: PENICK, INA
 RR#, St. Address, Box #: BOX 6220 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ELKHART, KS 67950- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
W	NW	NE	
4	SW	SE	X

4 DEPTH OF COMPLETED WELL 326 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 221 ft. below land surface measured on mo/day/yr 05/15/04
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 326 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 326 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 260 ft. to 320 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 326 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG
0	60	01 TOPSOIL 05 CLAY 02 FINE SAND
60	80	10 FINE-MEDSAND
80	100	02 FINE SAND 17 CLAY LAYERS
100	120	27 ROCK 22MED-COAR SAND 05 CLAY
120	140	05 CLAY 02 FINE SAND
140	160	10 FINE-MEDSAND 05 CLAY
160	180	05 CLAY 02 FINE SAND
180	200	02 FINE SAND
200	240	37 FIN-COAR SAN
240	280	37 FIN-COAR SAN 06 SMALL GRAVEL

FROM	TO	PLUGGING INTERVALS

RECEIVED
 OCT 27 2004
 BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/14/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Cook*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: MORTON	SE 1/4 SE 1/4 SE 1/4	9	T 35 S	R 43 W

2 WATER WELL OWNER:	Board of Agriculture, Division of Water Resources
PENICK, INA	
RR#, St. Address, Box #: BOX 6220	Application Number:
City, State, ZIP code: ELKHART, KS 67950-	

FROM	TO	LITHOLOGIC LOG
280	310	37 FIN-COAR SAN
310	340	20 RED SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:	
This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179	This Water Well Record was completed on (mo/day/yr) 07/14/04
under the business name of JOE'S WELL SERVICE, INC.	by (signature)