

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON SE 1/4 SW 1/4 NE 1/4 35 T 28 S R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/4 MILE WEST OF JOHNSON.

2 WATER WELL OWNER: REESE, EVELYN
 RR#, St. Address, Box #: 4728 S. LEWIS COURT Board of Agriculture, Division of Water Resources
 City, State, ZIP code: JOHNSON, KS 74105- Application Number: 9,525

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 631 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1	NW	NE
W	X	E
SW	SE	

WELL'S STATIC WATER LEVEL 319 ft. below land surface measured on mo/day/yr 12/19/92
 Pump test data: Well water was 374 ft. after 4 hours pumping 1200 gpm
 Estimated Yield 1200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 631 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 631 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 330 ft. to 350 ft., From 438 ft. to 448 ft.
 From 367 ft. to 397 ft., From 476 ft. to 626 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 631 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	30	04 SANDY CLAY			
30	57	06 VERY FN SAND 07 FINE SAND 01 CLAY			
57	87	01 CLAY 20 LIMESTONE			
87	97	05 SAND			
97	122	04 SANDY CLAY 07 FINE SAND			
122	141	07 FINE SAND 08 MEDIUM SAND			
141	197	04 SANDY CLAY 07 FINE SAND			
197	265	05 SAND 14 MED GRAVEL 30 ROCK & CLAY			
265	280	05 SAND 13 FINE GRAVEL 28 ROCK			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/23/92
 under the businessname of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 094 STANTON : SE 1/4 SW 1/4 NE 1/4 : 35 : T 28 S : R 41 W

2 WATER WELL OWNER: REESE, EVELYN
RR#, St. Address, Box # : 4728 S. LEWIS COURT Board of Agriculture, Division of Water Resources
City, State, ZIP code : JOHNSON, KS 74105- Application Number: 9,525

FROM	TO	LITHOLOGIC LOG
280	346	05 SAND 14 MED GRAVEL 28 ROCK
346	367	04 SANDY CLAY 07 FINE SAND
367	382	05 SAND 14 MED GRAVEL 28 ROCK
382	385	04 SANDY CLAY 05 SAND
385	397	05 SAND 13 FINE GRAVEL
397	438	01 CLAY 07 FINE SAND
438	447	05 SAND
447	467	01 CLAY
467	473	19 SHALE 20 LIMESTONE 23 SANDSTONE
473	511	01 CLAY 21 SHALE & LMST 23 SANDSTONE
511	553	23 SANDSTONE 19 SHALE 01 CLAY
553	562	20 LIMESTONE 19 SHALE 23 SANDSTONE
562	628	23 SANDSTONE 19 SHALE
628	640	20 LIMESTONE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/23/92
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*