

1 LOCATION OF WATER WELL: COUNTY: STANTON Fraction SE 1/4 SE 1/4 NW 1/4 Section Number 34 Township Number T 28 S Range Number R 42 W

Distance and direction from nearest town or city street address of well if located within city?
FROM WANTER - 3 N. ON BLACK TOP 1/2 WEST AND 1/4 NORTH

2 WATER WELL OWNER: LOADER, DELOH Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: HCR -- BOX 3 Application Number:
City, State, ZIP code: WANTER, KS 67862-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1 M I L E	NW	NE
W	SW	SE
	X	

4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 151 ft. below land surface measured on no/day/yr 11/17/95
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 10 in. to 290 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 260 ft. to 290 ft.
From 200 ft. to 255 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 40 ft. to 290 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE - NEW SITE
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL CLAY FINE - MED SAND			
40	60	FINE - MED SAND SMALL GRAVEL			
60	90	FINE - MED SAND CLAY LAYERS			
90	100	CLAY FINE SAND			
100	140	FINE SAND FINE - MED SAND VERY LOOSE			
140	158	FINE - MED SAND			
158	160	ROCK			
160	190	FINE SAND CLAY ROCK LAYERS			
190	240	SANDSTONE			
240	260	SANDSTONE TAN IN COLOR CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 11/17/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 12/29/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*

1 LOCATION OF WATER WELL: COUNTY: STANTON Fraction SE 1/4 SE 1/4 NW 1/4 Section Number 34 Township Number T 28 S Range Number R 42 W

2 WATER WELL OWNER: LOADER, DELOH Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: HCR -- BOX 3 Application Number:
City, State, ZIP code: WANTER, KS 67862-

FROM	TO	LITHOLOGIC LOG
260	280	SANDSTONE
280	290	SANDSTONE SAND
290	0	ROCK