

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 094 STANTON 1/4 1/4 SE 1/4 04 T 28 S R 42 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 9.25 MILES EAST AND 4.375 MILES NORTH OF JOHNSON.

2 WATER WELL OWNER: JOE BATTERTON Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: BOX 684  
 City, State, ZIP code : JOHNSON, KS 67855- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 330 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 245 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 245 ft. below land surface measured on mo/day/yr 05/04/92  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9.875 in. to 330 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 330 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 270 ft. to 330 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 330 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? WEST How many feet? 35

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	110	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
110	122	07 FINE SAND 08 MEDIUM SAND			
122	134	01 CLAY			
134	145	07 FINE SAND 08 MEDIUM SAND			
145	156	01 CLAY			
156	220	04 SANDY CLAY 05 SAND 20 LIMESTONE			
220	230	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY			
230	233	05 SAND			
233	243	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/04/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/08/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas B. Henkle

1 LOCATION OF WATER WELL:      Fraction      Section Number      Township Number      Range Number  
 COUNTY: 094 STANTON      1/4      1/4 SE      1/4      04      T 28      S      R 42      W

2 WATER WELL OWNER:      JOE BATTERTON  
 RR#, St. Address, Box #:      BOX 684      Board of Agriculture, Division of Water Resources  
 City, State, ZIP code      :      JOHNSON, KS      67855-      Application Number:

FROM	TO	LITHOLOGIC LOG
243	248	05 SAND
248	274	05 SAND 13 FINE GRAVEL
274	290	04 SANDY CLAY 07 FINE SAND
290	302	05 SAND 13 FINE GRAVEL
302	312	05 SAND 13 FINE GRAVEL 01 CLAY
312	330	19 SHALE 23 SANDSTONE
330	331	20 LIMESTONE
331	337	19 SHALE 20 LIMESTONE
337	342	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/04/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145      This Water Well Record was completed on (mo/day/yr) 06/08/92 under the business name of HENKLE DRILLING & SUPPLY      by (signature) *Douglas R. Henkle*