

1 LOCATION OF WATER WELL: COUNTY: STANTION Fraction NE 1/4 NE 1/4 SE 1/4 Section Number 32 Township Number T 28 S Range Number R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON CITY - 9 WEST, 1/2 SOUTH ON OLD HIGHWAY 160

2 WATER WELL OWNER: NICHOLS, ARLENE Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: BOX 41 Application Number:
 City, State, ZIP code: WANTER, KS 67862-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 290 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 198 ft. below land surface measured on no/day/yr 06/03/94
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 20 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 290 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOED
 Blank casing diameter 5 in. to 290 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 245 ft. to 295 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 290 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: WATERTIGHT SEW.
 Direction from well? NORTHWEST How many feet? 170

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	TOPSOIL			
3	40	CLAY SANDY CLAY			
40	62	CLAY SANDY CLAY			
62	83	MEDIUM SAND GRAVEL			
83	105	MEDIUM SAND			
105	124	MEDIUM SAND IN LAYERS			
124	145	SAND ROCK LAYER CLAY IN LAYERS			
145	172	CLAY			
172	205	SANDSTONE			
205	290	SANDSTONE TAN IN COLOR			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 06/03/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/11/94 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Creek*

1 LOCATION OF WATER WELL: COUNTY: STANTION Fraction NE 1/4 NE 1/4 SE 1/4 Section Number 32 Township Number T 28 S Range Number R 42 W

2 WATER WELL OWNER: NICHOLS, ARLENE Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: BOX 41 Application Number:
 City, State, ZIP code: WANTER, KS 67862-

FROM	TO	LITHOLOGIC LOG
290	305	SHALE