

1 COUNTY: STANTON WELL: NE 1/4 NE 1/4 Section Number 32 Township Number T 28 Range Number R 42 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JOHNSON CITY - 9W, 1/2S ON OLD HIGHWAY 160

2 WATER WELL OWNER: NICHOLS, MRS. ARLENE
 RR#, St. Address, Box #: BOX 41
 City, State, ZIP code : WALTER, KS 67862-
 Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE	SW	SE

4 DEPTH OF COMPLETED WELL 300 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 100 ft. below land surface measured on mo/day/yr 10/08/94
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 20 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 300 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 300 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 255 ft. to 295 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 24 ft. to 300 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 4 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? EAST How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	22	TOPSOIL BROWN CLAY			
22	30	SANDY CLAY CALACHIE CLAY			
30	112	PINE - MED SAND			
112	128	BROWN CLAY			
128	135	MEDIUM SAND GRAVEL			
135	157	YELLOW CLAY			
157	190	BROWN CLAY			
190	195	ROCK			
195	295	SANDSTONE			
295	300	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/08/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/26/94 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Critt*