

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Kingman		NE 1/4 SE 1/4	33	T 28 S	R 9
Distance and direction from nearest town or city street address of well if located within city? 9 Miles West, 5 Miles South, 1 MILE West, 3/4 Mile South Of Kingman, Kans.					
2 WATER WELL OWNER: Marjorie Kinsler & Bob Isley		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: 5408 NW 30th ST.		Application Number:			
City, State, ZIP Code: Kingman, Kans 67068					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 87' ft. ELEVATION:			
		Depth(s) Groundwater Encountered: 33' ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL: ft. below land surface measured on mo/day/yr Nov 21 - 1996			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield: 20 gpm; Well water was NA ft. after hours pumping gpm			
		Bore Hole Diameter: 7 7/8" in. to 87' ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes..... No ☒ ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes ☒ No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued ☒ Clamped			
1 Steel 3 RMP (SR)		Welded			
☒ PVC 4 ABS		Threaded			
Blank casing diameter: 5" in. to 77' ft., Dia		in. to ft., Dia			
Casing height above land surface: 24" in., weight 2.355 lbs./ft.		Wall thickness or gauge No. SDR 26			
TYPE OF SCREEN OR PERFORATION MATERIAL:		☒ PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		☒ 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS:		From 87' ft. to 77' ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
GRAVEL PACK INTERVALS:		From 87' ft. to 26' ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL:		☒ Bentonite 4 Other			
1 Neat cement 2 Cement grout					
Grout Intervals: From 26' ft. to ft., From 0' ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:		☒ Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage					
Direction from well? West		How many feet? 60'			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0'	8'	Top Soil.			
8'	30'	Clay.			
30'	33'	Clay.			
33'	38'	Fine Sand.			
38'	44'	Clay.			
44'	52'	Medium Course Sand.			
52'	62'	Clay.			
62'	68'	Medium Course Sand. (Dirty).			
68'	71'	Brown Clay.			
71'	87'	Course Sand (Very Clean).			
		Clay Bottom			
		Cement Plug In Bottom of Casing.			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) Nov 21 1996 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) Dec 22 1996 under the business name of Wells Drilling Co. by (signature) <i>Dal Wells</i>					