


1 LOCATION OF WATER WELL: Sedgwick	FRACTION NW 1/4 SE 1/4 NW 1/4	Section Number 9	Township Number T 29 S	Range Number R 1W E/W	
Distance and direction from nearest town or city street address of well if located within city? 3 3/4 miles West and 1 1/4 South of Haysville, Kansas					
2 WATER WELL OWNER: JAAX, Kevin RR#, ST. ADDRESS, BOX #: 9950 W. 71st S. CITY, STATE, ZIP CODE: Clearwater, Kansas 67026					
Board of Agriculture, Division of Water Resource Application Number: 41,472					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 93 ft. ELEVATION: Depth(s) groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 27 FT. BELOW LAND SURFACE MEASURED ON 05/11/1996 Pump test data: Well water was 65 ft. after 1 hours pumping 260 gpm Est. Yield gpm: Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 30 in. to 93 ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes _____ No X ; If yes, mo/day/yr sample was submitted _____ Water Well Disinfected? Yes X No _____				
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (Specify below) Welded 2 Fiberglass SDR-26 Threaded Blank casing Diameter 16 in. to 46 ft., Dia in. to _____ ft., Dia in. to _____ ft. Casing height above land surface 12 in., weight 19.750 lbs. / ft. Wall thickness or gauge No. .616 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 other (specify) _____ 12 None used (open hole) _____ SCREEN OR PERFORATION OPENING ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 10 Other (specify) _____ SCREEN-PERFORATION INTERVALS: from 46 ft. to 93 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: from 20 ft. to 93 ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other bentonite hole plug Grout Intervals: From 0 ft. to 20 ft. From _____ ft. to _____ ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandon water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ None Apparent Direction from well? _____ How many feet? _____					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	soil			
5	10	tan clay			
10	15	tan clay (hard)			
15	20	brown clay			
20	32	fine silty clayey sand			
32	63	sandy tan clay			
63	65	fine silty sand			
65	79	medium to coarse sand w/ clay lenses, loose, dirty drilled well, took water			
79	88	tan sandy clay			
88	93	medium to coarse sand w/ clay lenses, took water			
93	94	shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 05/11/1996 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This Water Well Record was completed on (mo/day/yr) 05/13/96 Under the business name of Harp Well & Pump Service, Inc. by (signature) <i>Jane Frederick</i>					