

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 1/4 SW 1/4	Section number 2	Township number T 29 S	Range number R 1 E
2. Distance and direction from nearest town or city: Street address of well location if in city: Hoover Rd. & 79th St. South			3. Owner of well: R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: Sketch map: Well No. 1 (TH 1-76)			6. Bore hole dia. 30 in. Completion date 4/7/76 Well depth 95 ft.		
5. Type and color of material			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material Stl Height: Above 24 in. Threaded ☐ Welded ☒ Surface 24 in. RMP ☐ PVC ☐ Weight 40 lbs./ft. Dia. 16 in. to 59 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 219		
			10. Screen: Manufacturer's name Doerr Metal Products Type Stl Dia. 16 " Slot/gauze 1/8 Length 36 " Set between 52 ft. and 72 ft. 77 ft. and 93 ft. Gravel pack? yes Size range of material 1/8-3/8		
			11. Static water level: 37 ft. below land surface Date 4/7/76 mo./day/yr.		
12. Pumping level below land surfaces: 50 ft. after 3 hrs. pumping 800 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1000 g.p.m.			13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.		
14. Well head completion: ☐ Pitless adapter 12 inches above grade			15. Well grouted? yes With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 20 ft.		
16. Nearest source of possible contamination: ft. 1300 Direction S Type Septic Well disinfected upon completion? ☒ Yes ☐ No			17. Pump: ☐ Not installed Manufacturer's name Layne Model number 10KEH HP 40 Volts ☐ Length of drop pipe 60 ft. capacity 600 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:			19. Remarks:		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 4/7/76		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5