

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction 1/4 C NE 1/4 NE 1/4	Section Number 13	Township Number T 29 S	Range Number R 1 E																																																
Distance and direction from nearest town or city street address of well if located within city? 2 S OF WEST EDGE OF HAYSVILLE, KS																																																					
2 WATER WELL OWNER: Slawson Drilling Company RR#, St. Address, Box #: Box 1131 City, State, ZIP Code: Great Bend, Kansas 67530			Lease: Love D # 2 Board of Agriculture, Division of Water Resources Application Number:																																																		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 72 ft. ELEVATION: Depth(s) Groundwater Encountered 1. 35 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 33 ft. below land surface measured on mo/day/yr 28 April 83 Pump test data: Well water was ft. after hours pumping gpm Est. Yield 100 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 10 in. to 72 ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No																																																			
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 5 in. to 52 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. 214 TYPE OF SCREEN OR PERFORATION MATERIAL: 7 Fiberglass 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 52 ft. to 72 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 10 ft. to 72 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage NONE Direction from well? How many feet?																																																					
<table><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td>0</td><td>10</td><td>Clay, tan</td><td></td><td></td><td></td></tr><tr><td>10</td><td>30</td><td>Sand, fine to med silty</td><td></td><td></td><td></td></tr><tr><td>30</td><td>35</td><td>Clay, tan=</td><td></td><td></td><td></td></tr><tr><td>35</td><td>50</td><td>Sand, med to coarse</td><td></td><td></td><td></td></tr><tr><td>50</td><td>52</td><td>Clay, tan</td><td></td><td></td><td></td></tr><tr><td>52</td><td>70</td><td>Sand, fine to med some coarse</td><td></td><td></td><td></td></tr><tr><td>70</td><td>73</td><td>Shale, blue</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	0	10	Clay, tan				10	30	Sand, fine to med silty				30	35	Clay, tan=				35	50	Sand, med to coarse				50	52	Clay, tan				52	70	Sand, fine to med some coarse				70	73	Shale, blue			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG																																																
0	10	Clay, tan																																																			
10	30	Sand, fine to med silty																																																			
30	35	Clay, tan=																																																			
35	50	Sand, med to coarse																																																			
50	52	Clay, tan																																																			
52	70	Sand, fine to med some coarse																																																			
70	73	Shale, blue																																																			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, 2 reconstructed, or 3 plugged under my jurisdiction and was completed on (mo/day/year) 28 APRIL 83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 6 JUL 83 under the business name of Central Well & Pump Inc. by (signature) <i>[Signature]</i> INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.																																																					