

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: <u>Sedgwick</u>		SE 1/4 SW 1/4 SE 1/4		13		T 29 S		R 1 E/W	
Distance and direction from nearest town or city street address of well if located within city?									
<u>Approx. 2 miles south and 1 1/4 mi. west of Haysville, KS</u>									
2 WATER WELL OWNER:		Kent Ott							
RR#, St. Address, Box # :		411 Mulvane							
City, State, ZIP Code :		Mulvane, KS 67110							
		Board of Agriculture, Division of Water Resources Application Number: <u>unknown</u>							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL <u>68</u> ft. ELEVATION <u>unknown</u>							
		Depth(s) Groundwater Encountered 1. <u>34</u> ft. 2. <u>34</u> ft. 3. <u>34</u> ft.							
		WELL'S STATIC WATER LEVEL <u>34</u> ft. below land surface measured on mo/day/yr <u>3/28/85</u>							
		Pump test data: Well water was <u>not ck'd</u> ft. after <u> </u> hours pumping <u> </u> gpm							
		Est. Yield <u>700</u> gpm: Well water was <u> </u> ft. after <u> </u> hours pumping <u> </u> gpm							
		Bore Hole Diameter <u>24</u> in. to <u>68</u> ft., and <u> </u> in. to <u> </u> ft.							
		WELL WATER TO BE USED AS:							
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) <u>2 Irrigation</u> 4 Industrial 7 Lawn and garden only 10 Observation well							
		Was a chemical/bacteriological sample submitted to Department? Yes <u> </u> No <u>X</u> ; If yes, mo/day/yr sample was submitted <u> </u>							
		Water Well Disinfected? Yes <u> </u> No <u>X</u>							
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u> </u> Clamped <u> </u> 1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) <u>Welded XX</u> 2 PVC 4 ABS 7 Fiberglass <u>Threaded</u>							
Blank casing diameter <u>16</u> in. to <u>48</u> ft., Dia. <u> </u> in. to <u> </u> ft., Dia. <u> </u> in. to <u> </u> ft.									
Casing height above land surface <u>12</u> in., weight <u>31.66</u> lbs./ft. Wall thickness or gauge No. <u>.188</u>									
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) <u> </u> 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)							
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) <u>DOERR BRIDGE SLOT</u>							
SCREEN-PERFORATED INTERVALS:		From <u>48</u> ft. to <u>60</u> ft., From <u> </u> ft. to <u> </u> ft. From <u> </u> ft. to <u> </u> ft., From <u> </u> ft. to <u> </u> ft.							
GRAVEL PACK INTERVALS:		From <u>10</u> ft. to <u>68</u> ft., From <u> </u> ft. to <u> </u> ft. From <u> </u> ft. to <u> </u> ft., From <u> </u> ft. to <u> </u> ft.							
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other <u> </u> Grout Intervals: From <u>0</u> ft. to <u>10</u> ft., From <u> </u> ft. to <u> </u> ft., From <u> </u> ft. to <u> </u> ft.							
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) <u>FIELD</u> 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage							
Direction from well? <u>all</u>		How many feet? <u> </u>							
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG				
0	10	Topsoil & brown clay							
10	26	Sand & gravel, fine							
26	28	Tan clay							
28	46	Sand & gravel, med. to fine clean w/few thin clay streaks, between 30' and 40'							
46	50	Sand & soft sandy yellow tan clay							
50	67	Sand & gravel, fine to very fine, some medium - clean & loose							
67	68	Tan clay							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>3/28/85</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>185</u> . This Water Well Record was completed on (mo/day/yr) <u>4/10/85</u> under the business name of <u>Clarke Well & Eq., Inc.</u> by (signature) <u>Clarke Well & Eq., Inc.</u>									
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.									

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4