

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 1/4 NW 1/4	Section number 24	Township number T 29 S	Range number R 1 W
2. Distance and direction from nearest town or city: West St. & 95th St. South Street address of well location if in city:			3. Owner of well: Bob Hay R.R. or street: Haysville, Kansas 67060 City, state, zip code:		
4. Locate with "X" in section below: Sketch map: Well No. 2 TH 1-76 6. Bore hole dia. 30 in. Completion date 10-12-76 Well depth 70 ft.			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material Stl. Height: Above 12 in. Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 31.75 lbs./ft. Dia. 16 in. to 47 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 188		
			From	To	10. Screen: Manufacturer's name Doerr Metal Products Type Stl. Dia. 16" Slot/gauze 1/8 Length 24' Set between 46 ft. and 70 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8 x 3/8
Soil			0	2	11. Static water level: ☐ mo./day/yr. 32 ft. below land surface Date 10-12-76
Brown clay			2	14	12. Pumping level below land surfaces: 47 ft. after 2 hrs. pumping 820 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 900 g.p.m.
Fine to coarse sand			14	27	13. Water sample submitted: ☐ Yes ☒ No Date ☐
Brown clay			27	29	14. Well head completion: ☐ Pitless adapter 12 inches above grade
Med. to coarse sand w/some fine gravel			29	70	15. Well grouted? Yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.
Green shale			70		16. Nearest source of possible contamination: ft. 1320 Direction EAST Type Feed lot Well disinfected upon completion? ☐ Yes ☒ No
					17. Pump: ☐ Not installed Manufacturer's name Layne Model number 12KLE HP 50 Volts 460 Length of drop pipe 60 ft. capacity 700 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 10-14-76 Authorized representative
18. Elevation:			19. Remarks:		
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5