


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>KINGMAN</u>		Fraction <u>SW NE NW</u> 1/4 1/4 1/4		Section number <u>30</u>	Township number T <u>29</u> S R <u>10 W</u> E/W
2. Distance and direction from nearest town or city: <u>1 W - 2 So. - 1 3/4 W of ST. Leo. Ks.</u>				3. Owner of well: <u>Wallace Ford</u> R.R. or street: City, state, zip code: <u>Nashville, Ks. 67112</u>	
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>28</u> in. Completion date <u>14 DEC</u> Well depth <u>82</u> ft.	
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
<u>TOP</u>		<u>0'</u>	<u>8'</u>	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<u>Clay</u>		<u>8'</u>	<u>18'</u>	9. Casing: Material <u>STEEL</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>16</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>82</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gauge No. <u>7 Ga.</u>	
<u>COURSE SAND</u>		<u>18'</u>	<u>20'</u>	10. Screen: Manufacturer's name <u>W.A. BROWN ENTERPRISES</u> Type <u>ST. FREE-FLOW</u> Dia. <u>16"</u> Slot/gauze <u>1/4</u> Length <u>40'</u> Set between <u>42</u> ft. and <u>82</u> ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/8 - 3/8</u>	
<u>Clay</u>		<u>20'</u>	<u>25'</u>	11. Static water level: <u>10'</u> ft. below land surface Date <u>12/14/76</u> mg./day/yr.	
<u>COURSE SAND</u>		<u>25'</u>	<u>35'</u>	12. Pumping level below land surfaces: <u>29</u> ft. after <u>2</u> hrs. pumping <u>820</u> g.p.m. <u>32</u> ft. after <u>3</u> hrs. pumping <u>960</u> g.p.m. Estimated maximum yield <u>1100</u> g.p.m.	
<u>COURSE SAND-FINE GRAVEL</u>		<u>35'</u>	<u>58'</u>	13. Water sample submitted: <u>Yes</u> <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>12/14/76</u> mo./day/yr.	
<u>Clay</u>		<u>58'</u>	<u>64'</u>	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>16</u> inches above grade	
<u>COURSE SAND</u>		<u>64'</u>	<u>82'</u>	15. Well grouted? <input type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>3</u> ft. to <u>14</u> ft.	
<u>White clay</u>		<u>82'</u>		16. Nearest source of possible contamination: ft. <u>2600</u> Direction <u>NORTH</u> Type <u>FARM ST</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
				17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>JACUZZI</u> Model number <u>60</u> HP <u>1/2</u> Volts <u>115</u> Length of drop pipe <u>60</u> ft. capacity <u>850</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Wells Drilling Co.</u> <u>112</u> Business name License No. Address <u>1030 Hiway 54 EAST</u> Signed <u>Dal Wells</u> Date <u>12/14/76</u> Authorized representative	