

USE TYPEWRITER OR BALL
POINT PEN. PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction 1/4 c 1/4 se 1/4	Section number 24	Township number 29 T 27 S	Range number 11 R 11 E W				
2. Distance and direction from nearest town or city: 4-E 2-N 1/2-E north side from Isable, Ks. Street address of well location if in city:				3. Owner of well: Charley Ridge R.R. or street: none City, state, zip code: Isabel, Kansas 67065						
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile</div>				NW	NE	SW	SE	Sketch map: <div style="text-align: center;">1 Mile</div>		
NW	NE									
SW	SE									
5. Type and color of material				From	To	6. Bore hole dia. 29 in. Completion date 5-11-79 Well depth 80 ft.				
sandy top soil				0	2	7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary				
orange sand clay				2	8	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other				
brown & white clay				8	11	9. Casing: Material steel Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 18 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 16 in. to 80 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gauge No. 7				
sand & gravel w/clay mixed				11	14	10. Screen: Manufacturer's name Doerrs Type steel Dia. <input type="checkbox"/> Slot/ 3/16 Length 32 Set between 48 ft. and 80 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 3/4 3/8				
sand & gravel				14	53	11. Static water level: <input type="checkbox"/> mo./day/yr. 17 ft. below land surface Date 1-7-77				
clay mixed w/sand & gravel				53	55	12. Pumping level below land surfaces: 44 ft. after 1 hrs. pumping 600 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 800 g.p.m.				
clay				55	56	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 1-7-77				
sand & gravel				56	80	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade				
clay				80	123	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.				
red bed				✓ 123	125	16. Nearest source of possible contamination: ft. 150 Direction North gas well Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
(Use a second sheet if needed)						17. Pump: Not installed Manufacturer's name W.I.R. Model number 3-12CM HP 80 Volts <input type="checkbox"/> Length of drop pipe 70 ft. capacity 800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
18. Elevation: 1967 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: 28604 29 11 24 NDY					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Great Bend, Ks. 67530 Signed Shadyk, Topeka Date 5-15-79 Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5