


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction 1/4 NW 1/4 NE 1/4	Section number 1	Township number T 29 S	Range number R 12 E/W
2. Distance and direction from nearest town or city: 13 mi. Southeast of Pratt, KS Street address of well location if in city:				3. Owner of well: John Neumann R.R. or street: (?) City, state, zip code: Isabel, KS 67065		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W 1 Mile E S</div> 				6. Bore hole dia. 24 in. Completion date 5-17-76 Well depth 182 ft.		
5. Type and color of material				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
				8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
				9. Casing: Material Steel Height Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 30.3 lbs./ft. Dia. 16 in. to 102 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 7 ga.		
				10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot/gauze 1/8 Length 80' Set between 102 ft. and 182 ft. ft. and <input type="checkbox"/> ft. Gravel pack? Yes Size range of material 3/8-200		
Top soil				From	To	11. Static water level: 81 ft. below land surface Date 5-4-76 mo./day/yr.
Sand & sandy clay				0	3	12. Pumping level below land surfaces: N/C ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.
Brown & white clay & limestone				3	15	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> mo./day/yr.
Sand, gravel & limestone				15	60	14. Well head completion: 12 inches above grade <input type="checkbox"/> Pitless adapter
Brown & white clay & limestone				60	78	15. Well grouted? Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
Sand & gravel				78	95	16. Nearest source of possible contamination: NONE KNOWN ft. Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Brown & white clay & hard limestone				95	120	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name FMC Corp./Peerless Model number 12LB-3 HP 80 Volts <input type="checkbox"/> Length of drop pipe 120 ft. capacity 900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Brown clay & limestone				120	132	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed D.W. Clarke Date 5-28-76 Authorized representative
Sand, gravel & limestone & streaks				132	146	
				146	152	
				152	182	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5