

[1] LOCATION OF WATER WELL: County: Pratt		Fraction SW ¼ NW ¼ E/W	Section Number 21	Township Number T 29 S	Range Number R 13W E/W
Distance and direction from nearest town or city street address of well if located within city? 4E Coats, KS					
[2] WATER WELL OWNER: Matt Novotny		Sterling Drilling Co.		Novotny 'B' #1 Board of Agriculture, Division of Water Resources	
RR#, St. Address, Box #: 90289 S 1st Ave.		P. O. Box 1006			
City, State, ZIP Code :Pratt, Ks. 67124		Pratt, KS 67124		Application Number: 970101	
[3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		[4] DEPTH OF COMPLETED WELL 205 ft. ELEVATION: unknown			
A diagram showing a section box divided into four quadrants labeled NW, NE, SE, and SW. An 'X' marks the location at the intersection of the center vertical dashed line and the bottom horizontal solid line.		Depth(s) Groundwater Encountered 1. 70 ft. 2. .ft. 3. .ft.			
		WELL'S STATIC WATER LEVEL .. 70 .. ft. below land surface measured on mo/day/yr 3-17-97			
		Est. Yield .. 60 gpm; Well water was .ft. after hours pumping gpm			
		Bore Hole Diameter .. 8 ..in. to 205 ..ft., and ..in. to ..ft.			
TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped Welded Threaded			
Blank casing diameter .. 5 ..in. to 165 ..ft., Dia ..in. to ..ft., Dia ..in. to ..ft.					
Casing height above land surface .. 12 ..in.; weight 2.8 lbs./ft.		Wall thickness or gauge No. Sch. 40			
TYPE OF SCREEN OR PERFORATION MATERIAL:		SCREEN OR PERFORATION OPENINGS ARE:			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		10 Asbestos-cement			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		11 Other (specify)			
		12 None used (open hole)			
SCREEN-PERFORATED INTERVALS:		GRAVEL PACK INTERVALS:			
From 165 ft. to 205 ft.		From 20 ft. to 205 ft.			
[6] GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 20 ft.		What is the nearest source of possible contamination:			
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
Direction from well? West		How many feet? 125			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	6	Top soil and clay			
6	13	Sand and gravel			
13	35	Clay			
35	205	Sand and gravel			
[7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3-17-97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 186 This Water Well Record was completed on (mo/day/yr) 3-18-97 under the business name of Kelly's Water Well Service, Inc. by (signature) Kathryn A Good					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					