

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Pratt		SW 1/4 NW 1/4 SE 1/4	12	T 29 S	R 14 E (W)
Distance and direction from nearest town or city street address of well if located within city? 2E 1 1/4 N 1/2 W OF COATS, KS					
2 WATER WELL OWNER: Seagull Operating Co.					
RR#, St. Address, Box # : 1215 Mid South Tower			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : Shreveport, Louisiana 71101			Lease; Prather #1 Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 160 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 110 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 110 ft. below land surface measured on mo/day/yr 6 July 82			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield 80 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: 10 in. to 160 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		1 Domestic 3 Feedlot (6) Oil field water supply 9 Dewatering 11 Injection well 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well 12 Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued X Clamped (2) PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded Blank casing diameter 5 in. to 140 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass (7) PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) SCREEN OR PERFORATION OPENINGS ARE: 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped (8) Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From 140 ft. to 160 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 10 ft. to 160 ft., From ft. to ft.					
6 GROUT MATERIAL: (1) Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) NONE 13 Insecticide storage					
Direction from well? How many feet?					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Top soil			
2	35	Clay, dark brown			
35	55	Clay, gray			
55	75	Sand, fine to coarse to fine to med gravel, tight			
75	105	Clay, brown and tan with white caliche			
105	160	Sand, med to coarse to med to coarse gravel			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6 July 82 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 25 Oct 82 under the business name of Central Well & Pump Inc. by (signature) BB Anonmehl					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

29

R

14

E

SEC.

12

SW 1/4

NW 1/4

SE 1/4

1/4