

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 049 KIOWA SE 1/4 NW 1/4 SW 1/4 17 T 29 S R 16 W

Distance and direction from nearest town or city street address of well if located within city?
2 1/2 E, 6 1/2 S. OF HAVILAND, KS

2 WATER WELL OWNER: WHITNEY, KURT 121 Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: R.R. Application Number:
City, State, ZIP code : HAVILAND, KS 67059-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 50 ELEVATION:
Depth(s) Groundwater Encountered 1. 18 ft. 2. ft. 3. ft.
WELL'S STATIC WATER LEVEL 18 ft. below land surface measured on mo/day/yr
Pump test data: Well water was ft. after hours pumping gpm
Estimated Yield gpm: Well water was ft. after hours pumping gpm
Bore Hole Diameter 8.75 in. to 50 ft., and in. to ft.
WELL WATER TO BE USED AS: 01 DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 40 ft., Dia in. to ft., Dia in. to ft.
Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 40 ft. to 50 ft., From ft. to ft.
From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 25 ft. to 50 ft., From ft. to ft.
From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
What is the nearest source of possible contamination: 01 SEPTIC TANK
Direction from well? SW How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	8	SILT & SAND			
8	18	05 SAND AND 17 GRAVEL			
18	25	BLACK CLAY			
25	48	05 SAND AND 17 GRAVEL			
48	50	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 1 /14/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 03/07/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse