

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SE 1/4 SW 1/4	1/4	Section number 20	Township number T 29 S	Range number R 2	X W
2. Distance and direction from nearest town or city: Street address of well location if in city: 199th St. W. & 103rd St. S., Wichita					3. Owner of well: Vulcan Materials Company R.R. or street: P. O. Box 12283 City, state, zip code: Wichita, Kansas 67277			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Pauley Well No. 8					6. Bore hole dia. 42 in. Completion date 8/8/78 Well depth 40 ft.			
5. Type and color of material					From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
							8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
							9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 60 in. RMP ☐ PVC ☐ Weight 62.6 lbs./ft. Dia. 16 in. to 25 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 0.375	
							10. Screen: Manufacturer's name Layne Type WW Dia. 16" Slot/gauze 0.100" Length 15' Set between 25 ft. and 40 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8"	
							11. Static water level: ☐ mo./day/yr. 12.5 ft. below land surface Date 6/30/78	
							12. Pumping level below land surfaces: 19 ft. after 1 hrs. pumping 150 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 200 g.p.m.	
							13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
							14. Well head completion: ☐ Pitless adapter 60 inches above grade	
							15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
							16. Nearest source of possible contamination: ND ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No	
							17. Pump: ☐ Not installed Manufacturer's name Layne Model number 8 URHC HP 15 Volts 460 Length of drop pipe 30 ft. capacity 200 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)								
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley		19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed [Signature] Date 8/14/78 Authorized Representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5