

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction SE 1/4 SW 1/4 1/4	Section number 20	Township number T 29 S R 2	Range number 2
2. Distance and direction from nearest town or city: Clearwater, Kansas Street address of well location if in city:		3. Owner of well: Vulcan Materials Company R.R. or street: P. O. Box 545 City, state, zip code: Wichita, Kansas 67202			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: Pauley Well No. 7		6. Bore hole dia. 42 in. Completion date 10/4/76 Well depth 36 ft.	
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Fine silty sand		0	12	8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Brown clay		12	14	9. Casing: Material Stl Height: Above surface Threaded ☐ Welded ☒ Surface 24 in. RMP ☐ PVC ☐ Weight 62.6 lbs./ft. Dia 16 in. to 23 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 375	
				10. Screen: Manufacturer's name Mustang	
				Type WW Dia. 16" Slot/gauze 0.100" Length 15' Set between 23 ft. and 38 ft. ft. and 38 ft.	
				Gravel pack? ☒ Size range of material 3/8"	
				11. Static water level: 21 ft. below land surface Date 10/4/76	
				12. Pumping level below land surfaces: ft. after 3 hrs. pumping 100 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 300 g.p.m.	
				13. Water sample submitted: Yes ☒ No ☐ Date 10/19/76	
				14. Well head completion: ☒ Pitless adapter 24 inches above grade	
				15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.	
				16. Nearest source of possible contamination: ft. 600 Direction N. Type River Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: Not installed Manufacturer's name Layne & Bowler Model number 82268 HP 15 Volts 440 Length of drop pipe 31 ft. capacity 200 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
		(Use a second sheet if needed)			
18. Elevation:	19. Remarks: Water Supply for Salt Wash Out Wells		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. Address Wichita, Kansas Signed Dr. [Signature] Date 10-27-76 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5