


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82g-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

BilledTo:LeStage Plbg.

County Sedgwick		Fraction 1/4NW 1/4SW 1/4	Section number 24	Township number T 29 S R 2W E/W	Range number
1. Location of well: 135th West and 103rd St. South, North on east side of the road.			3. Owner of well: Bill Machart R.R. or street: 622 Elaine City, state, zip code: Clearwater, Kansas		
2. Distance and direction from nearest town or city: Clearwater, Kansas			3. Owner of well: Bill Machart R.R. or street: 622 Elaine City, state, zip code: Clearwater, Kansas		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 3-24-77 Well depth 66 ft.
Topsoil			0	3	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Clay			3	29	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☒ Lawn ☐ Oil field water ☐ Other
Fine Sand			29	45	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 66 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. 200
Shale			45	66	10. Screen: Manufacturer's name Sunflower Plastic Type Styrene Dia. 5" Slot 1/16" .06 Length 28' Set between 38 ft. and 66 ft. Gravel pack? yes Size range of material 1/4-1/8"
					11. Static water level: 30 ft. below land surface Date 3-24-77 no./day/yr.
					12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
					13. Water sample submitted: _____ mo./day/yr. ☐ Yes ☐ No Date _____
					14. Well head completion: ☒ Pitless adapter 12 inches above grade
					15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
					16. Nearest source of possible contamination: NONE ft. _____ Direction _____ Type _____ Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: Manufacturer's name Sta-Rite Model number 20P4C0 HP 1/2 Volts _____ Length of drop pipe 45 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
18. Elevation:			19. Remarks: Septic system not Installed when the well was drilled. No apparent source for contamination.		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 3-24-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5