

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: KIOWA SW 1/4 SW 1/4 NW 1/4 19 T 29 S R 20 W

Distance and direction from nearest town or city street address of well if located within city?
 4 1/2 MILES WEST, 4 1/2 MILES SOUTH OF MULLINVILLE

2 WATER WELL OWNER: VICE, LEROY Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: PO BOX 236 Application Number:
 City, State, ZIP code: BUCKLIN, KS 67834-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \									
	NW	NE							
1	X								
M i l e	W		E						
	SW	SE							
\ /									

4 DEPTH OF COMPLETED WELL 225 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 140 ft. below land surface measured on mo/day/yr 09/15/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8.75 in. to 225 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: LIVESTOCK
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 205 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 205 ft. to 225 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 225 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL How many feet? 100
 Direction from well? SOUTH

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	120	TAN CLAY			
120	225	SAND AND GRAVEL			
225	230	TAN CLAY			
230	236	SAND AND GRAVEL			
236	237	TAN CLAY			
237	244	SAND AND GRAVEL			
244	245	GRAY SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/15/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 12/09/04 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hays