

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 029 FORD NE 1/4 SW 1/4 SW 1/4 32 T 29 S R 21 W

Distance and direction from nearest town or city street address of well if located within city?

5 S. 1/2 W. OF BUCKLIN, KS.

2 WATER WELL OWNER: ROGER CARLIN 227

RR#, St. Address, Box #: 124 S. CHICAGO

Board of Agriculture, Division of Water Resources

City, State, ZIP code : BUCKLIN, KS 67834-

Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8

4 DEPTH OF COMPLETED WELL 240 ELEVATION:
 Depth(s) Groundwater Encountered 1. 140 ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 140 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm

Estimated Yield gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 8.75 in. to 240 ft., and in. to ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 220 ft., Dia in. to ft., Dia in. to ft.

Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26-21

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 220 ft. to 240 ft., From ft. to ft.

From ft. to ft., From ft. to ft.

GRAVEL PACK INTERVALS: From 25 ft. to 240 ft., From ft. to ft.

From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 25 ft. to 240 ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination: 01 SEPTIC TANK

Direction from well? NE How many feet? 125

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	170	TAN CLAY			
170	198	05 SAND AND 17 GRAVEL			
198	214	GREY CLAY			
214	240	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 9 /11/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 10/05/93 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse