


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

18?

1. Location of well:		County: Ford	Fraction: NE 1/4 NE 1/4 NE 1/4	Section number: 8	Township number: 29	Range number: X22-22
2. Distance and direction from nearest town or city: N, side of Kingsdown Street address of well location if in city: Kans				3. Owner of well: Kay DART R.R. or street: Kingsdown City, state, zip code: Kansas		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 5 1/4 in. Completion date 9-10-78 Well depth 207 ft.		
				7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material				From	To	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Top Soil				0	2	9. Casing: Material PI Height: Above or below Threaded ☐ Welded ☒ Surface 14 in. RMP ☒ PVC ☐ Weight 1.5 lbs./ft. Dia. 5 1/4 in. to 207 ft. depth Wall Thickness: inches or Dia. 5 1/4 in. to 207 ft. depth gage No. 200
Bl. Hard Pan				2	3	10. Screen: Manufacturer's name Sunflower Plastics Type RMP Dia. 5 1/4 Slot gauge 1/8 Length 20 Set between 187 ft. and 207 ft. Gravel pack? Yes Size range of material 4x2
Lt. Tan Clay				3	102	11. Static water level: 164 ft. below land surface Date 9-10-78 mo./day/yr.
Tough Clay Tan				102	104	12. Pumping level below land surfaces: 164 ft. after 1 hrs. pumping 10 g.p.m. ft. after 1 hrs. pumping 10 g.p.m. Estimated maximum yield 20 g.p.m.
Lt. Tan Clay SOFT				104	119	13. Water sample submitted: Yes ☒ No ☐ Date 9-10-78 mo./day/yr.
Tough Clay Tan				119	126	14. Well head completion: ☒ Pitless adapter 14 Inches above grade
Lt. Tan Clay SOFT				126	142	15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 7 ft. to 14 ft.
Tough Clay Tan				142	145	16. Nearest source of possible contamination: Septic ft. 65 Direction N Type Septic Well disinfected upon completion? ☒ Yes ☐ No
Lt. Tan Clay				145	157	17. Pump: FLINT & WALLING Not installed Manufacturer's name FLINT & WALLING Model number 7B412 HP 3/4 Volt 230 Length of drop pipe 190 ft. capacity 10 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
Gravel Five To 1/2				157	207	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Carl Rayse Business name Willow 224 603 Address 2 Maple Greensburg Ks License No. Signed Carl Rayse Date 9-10-78 Authorized representative
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						