

1 LOCATION OF WATER WELL	Fraction	Section Number	Township Number	Range Number
County: Ford	SW 1/4 SW 1/4 SE 1/4	9	T 29 S	R 22 E/W

Distance and direction from nearest town or city?

1 1/2 East of Kingsdown, Kansas

Street address of well if located within city?

2 WATER WELL OWNER:	Samuel Gary Oil Company	WILLIAMS 9-15
RR#, St. Address, Box # :	#4 Inverness Court East	Board of Agriculture, Division of Water Resources
City, State, ZIP Code :	Englewood, Colorado 80112	Application Number: ----

3 DEPTH OF COMPLETED WELL	210	ft. Bore Hole Diameter	7 7/8	in. to	210	ft. and		in. to		ft.
Well Water to be used as:	5 Public water supply	8 Air conditioning	11 Injection well							
1 Domestic	3 Feedlot	XX Oil field water supply	9 Dewatering	12 Other (Specify below)						
2 Irrigation	4 Industrial	7 Lawn and garden only	10 Observation well							
Well's static water level	143	ft. below land surface measured on	March	month	19	day	1981	year		
Pump Test Data		Well water was		ft. after		hours pumping		gpm		
Est. Yield	50	gpm	Well water was		ft. after		hours pumping		gpm	

4 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	Casing Joints: Glued XXX Clamped		
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded	
XX2 PVC	4 ABS	7 Fiberglass		Threaded	
Blank casing dia	5	in. to	170	ft. Dia	
Casing height above land surface	12	in. weight	2.8	lbs./ft. Wall thickness or gauge No	
TYPE OF SCREEN OR PERFORATION MATERIAL:	XX7 PVC	10 Asbestos-cement			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)	
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)	
Screen or Perforation Openings Are:	5 Gauzed wrapped	XXX8 Saw cut	11 None (open hole)		
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes		
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)		
Screen-Perforation Dia	5	in. to	210	ft. Dia	
Screen-Perforated Intervals:	From	170	ft. to	210	ft.
Gravel Pack Intervals:	From	14	ft. to	210	ft.

5 GROUT MATERIAL:	XX Neat cement	2 Cement grout	3 Bentonite	4 Other			
Grouted Intervals: From	4	ft. to	14	ft. From			
What is the nearest source of possible contamination:	10 Fuel storage	14 Abandoned water well					
1 Septic tank	4 Cess pool	7 Sewage lagoon	11 Fertilizer storage	XX5 Oil well/Gas well			
2 Sewer lines	5 Seepage pit	8 Feed yard	12 Insecticide storage	16 Other (specify below)			
3 Lateral lines	6 Pit privy	9 Livestock pens	13 Watertight sewer lines				
Direction from well	Southeast	How many feet	150	? Water Well Disinfected? Yes XXX No			
Was a chemical/bacteriological sample submitted to Department? Yes	No	XXX		If yes, date sample			
was submitted	month	day	year	Pump Installed? Yes XXX (temporarily)			
If Yes: Pump Manufacturer's name	Aermotor	Model No.	SE50-500	HP	5	Volts	230
Depth of Pump Intake	189	ft.	Pumps Capacity rated at	50	gal./min.		
Type of pump:	XXX Submersible	2 Turbine	3 Jet	4 Centrifugal	5 Reciprocating	6 Other	

6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on	March	month	10	day	1981	year
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No.	252					
This Water Well Record was completed on	March	month	11	day	1981	year
name of	Friesen Windmill & Supply Inc.	by (signature)				

7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
	0	1	Topsoil			
	1	155	Clay			
	155	210	Med. to Lar. Sand			
	210	220	Black Shale			

1 Mile

ELEVATION: Upland

Depth(s) Groundwater Encountered	1. Not available	ft. 3	ft. 4	(Use a second sheet if needed)
INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.				