


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: FORD		SE 1/4 NE 1/4 NE 1/4	18	T 29 S	R 22 EW
Distance and direction from nearest town or city street address of well if located within city? E. Edge of Kingsdown Kansas					
2 WATER WELL OWNER: ROGER MOLLIHAN					
RR#, St. Address, Box # : City, State, ZIP Code : Kingsdown Kansas					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 220 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 162 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 162 ft. below land surface measured on mo/day/yr 10-7-81			
		Pump test data: Well water was 162 ft. after 1 hours pumping 10 gpm			
		Est. Yield 20 gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 8 3/4 in. to 220 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED:					
1 Steel 2 PVC 3 RMP (SR) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) CASING JOINTS: Glued X Clamped Welded Threaded					
Blank casing diameter 5 in. to 200 ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface 12 in., weight lbs./ft. Wall thickness or gauge No. SDR-26					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 2 Brass 3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 7 PVC 8 RMP (SR) 9 ABS 10 Asbestos-cement 11 Other (specify) 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 2 Louvered shutter 3 Mill slot 4 Key punched 5 Gauzed wrapped 6 Wire wrapped 7 Torch cut 8 Saw cut 9 Drilled holes 10 Other (specify) 11 None (open hole)					
SCREEN-PERFORATED INTERVALS: From 200 ft. to 220 ft., From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 185 ft. to 200 ft., From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other					
Grout Intervals: From 4 ft. to 14 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank 2 Sewer lines 3 Watertight sewer lines 4 Lateral lines 5 Cess pool 6 Seepage pit 7 Pit privy 8 Sewage lagoon 9 Feedyard 10 Livestock pens 11 Fuel storage 12 Fertilizer storage 13 Insecticide storage 14 Abandoned water well 15 Oil well/Gas well 16 Other (specify below)					
Direction from well? NW How many feet? 50					
LITHOLOGIC LOG					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Top Soil			
2	157	Tan Clay			
157	168	Sand			
168	180	Tan Clay			
180	201	FINE Sand			
201	220	Gravel			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-7-81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11-3-81 under the business name of Carl Kayse Water Well Serv. by (signature) Carl Kayse					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					