


1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Ford		$W\frac{1}{2}$ $\frac{1}{4}$ SW $\frac{1}{4}$ SW $\frac{1}{4}$	34	T 29 S	R 22 EW
Distance and direction from nearest town or city street address of well if located within city? 3 3/4 south 2 1/8 east of Kingsdown					
2 WATER WELL OWNER:		Pickrell Drilling Box 1303 Great Bend, Ks. 67530 Board of Agriculture, Division of Water Resources Application Number: T89-308			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL... 190 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL ... 104 ft. below land surface measured on mo/day/yr 7-14-89 Pump test data: Well water was ft. after hours pumping gpm Est. Yield na gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter... 10 in. to 190 ft., and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No <u>x</u> ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes <u>hth</u> No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u>x</u> Clamped Welded Threaded			
1 Steel 3 RMP (SR) 2 PVC 4 ABS		5 Wrought iron 8 Concrete tile 6 Asbestos-Cement 9 Other (specify below)			
Blank casing diameter 5 in. to 150 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface 18 in., weight 258 lbs./ft. Wall thickness or gauge No.		7 PVC 10 Asbestos-cement 8 RMP (SR) 11 Other (specify) 9 ABS 12 None used (open hole)			
TYPE OF SCREEN OR PERFORATION MATERIAL:		SCREEN OR PERFORATION OPENINGS ARE:			
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 9 ABS 12 None used (open hole)		5 Gauzed wrapped 8 Saw cut 11 None (open hole) 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)			
SCREEN-PERFORATED INTERVALS: From 150 ft. to 190 ft., From ft. to ft. From ft. to ft., From ft. to ft.		GRAVEL PACK INTERVALS: From 20 ft. to 190 ft., From ft. to ft. From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other		Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft.			
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well 11 Fuel storage 15 Oil well/Gas well 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage			
1 Septic tank 4 Lateral lines 7 Pit privy 2 Sewer lines 5 Cess pool 8 Sewage lagoon 3 Watertight sewer lines 6 Seepage pit 9 Feedyard		Direction from well? west How many feet? 100			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Top soil			
3	60	Brown clay			
60	70	Sand and gravel			
70	80	Brown clay with streaks of sand & rock			
80	130	Brown clay with streaks of sand			
130	187	Sand and gravel			
187	190	Shale			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7-14-89 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/yr) 7-27-89 under the business name of Rosencrantz-Bemis by (signature) Fredia Watson					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320. Telephone: 913-296-5514. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4