

247

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: FORD	Fraction NW 1/4 NW 1/4 NE 1/4	Section Number 16	Township Number T 29 S	Range Number R 22 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
1.5 MILES EAST OF KINGSDOWN

2 WATER WELL OWNER: RR#, St. Address, Box # : 12667 WINDY ROAD City, State, ZIP code : BUCKLIN, KS 67834-	RICHTER, MARVIN Board of Agriculture, Division of Water Resources Application Number:
---	---

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 220 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.																		
<table border="1"><tr><td>1</td><td>---</td><td>NW</td><td>---</td><td>NE</td><td>---</td></tr><tr><td>Mile</td><td>W</td><td>---</td><td>---</td><td>---</td><td>E</td></tr><tr><td></td><td>---</td><td>SW</td><td>---</td><td>SE</td><td>---</td></tr></table>	1	---	NW	---	NE	---	Mile	W	---	---	---	E		---	SW	---	SE	---	WELL'S STATIC WATER LEVEL 169 ft. below land surface measured on mo/day/yr 07/14/05 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 8.75 in. to 220 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
1	---	NW	---	NE	---														
Mile	W	---	---	---	E														
	---	SW	---	SE	---														

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT	

SCREEN PERFORATED INTERVALS:	From 200 ft. to 220 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 24 ft. to 220 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE	
Grout Intervals: From 4 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: SEPTIC TANK	
Direction from well? NORTH	How many feet? 150

FROM 0 166 217	TO 166 217 220	LITHOLOGIC LOG TAN CLAY SAND AND GRAVEL GRAY SHALE	FROM	TO	PLUGGING INTERVALS
-------------------------	-------------------------	---	------	----	--------------------

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/14/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 08/22/05 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayes
--