

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 SW 1/4 NW 1/4 7 T 29 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - 13 SOUTH ON HIGHWAY 183 - 1 E & 1/2 SOUTH

2 WATER WELL OWNER: HARRIS, TRUDY
 RR#, St. Address, Box #: 1205 SUNNYSIDE DRIVE Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8	9	10

4 DEPTH OF COMPLETED WELL 205 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 144 ft. below land surface measured on mo/day/yr 05/10/95
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 25 gpm Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 205 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 205 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.
 From 180 ft. to 200 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 205 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	30	TOPSOIL SANDY CLAY			
30	115	BROWN CLAY			
115	135	SAND GRAVEL			
135	140	SAND CLAY			
140	150	MEDIUM SAND SMALL GRAVEL			
150	160	CLAY SAND			
160	185	CALACHIE CLAY			
185	195	BROWN CLAY			
195	225	RED BED CLAY			
225	240	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/10/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/11/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*