

1 LOCATION OF WATER WELL: COUNTY: FORD		Fraction <i>SW 1/4 SW 1/4 SE 1/4</i>	Section Number 25	Township Number T 29 S	Range Number R 24 E																																																																		
Distance and direction from nearest town or city street address of well if located within city? 208 BLOOM ST. BLOOM, KS 67833-																																																																							
2 WATER WELL OWNER: HELLSTORM, AL RR#, St. Address, Box #: 208 BLOOM ST. City, State, ZIP code : BLOOM, KS 67833-		Board of Agriculture, Division of Water Resources Application Number:																																																																					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 240 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.																																																																					
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:5%; text-align:center;">1</td> <td style="width:5%; text-align:center;">2</td> <td style="width:5%; text-align:center;">3</td> <td style="width:5%; text-align:center;">4</td> <td style="width:5%; text-align:center;">5</td> <td style="width:5%; text-align:center;">6</td> <td style="width:5%; text-align:center;">7</td> <td style="width:5%; text-align:center;">8</td> <td style="width:5%; text-align:center;">9</td> <td style="width:5%; text-align:center;">10</td> </tr> <tr> <td style="text-align:center;">NW</td> <td></td> <td style="text-align:center;">NE</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td style="text-align:center;">SW</td> <td></td> <td style="text-align:center;">SE</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		1	2	3	4	5	6	7	8	9	10	NW		NE								SW		SE								WELL'S STATIC WATER LEVEL 167 ft. below land surface measured on no/day/yr 11/02/94 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 9 in. to 240 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, no/day/yr sample was submitted Water well disinfected? Yes																																							
		1	2	3	4	5	6	7	8	9	10																																																												
		NW		NE																																																																			
		SW		SE																																																																			
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 5 in. to 240 ft., Dia in. to 0 ft., Dia in. to 0 ft. Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: SAW CUT																																																																							
SCREEN PERFORATED INTERVALS: From 180 ft. to 240 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 24 ft. to 240 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.																																																																							
6 GROUT MATERIAL BENTONITE Grout Intervals: From 4 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: ABANDONED WELL Direction from well? WEST How many feet? 18																																																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>20</td><td>TOPSOIL SANDY CLAY</td><td></td><td></td><td></td></tr> <tr><td>20</td><td>45</td><td>CALACHIE CLAY</td><td></td><td></td><td></td></tr> <tr><td>45</td><td>50</td><td>SANDY CLAY</td><td></td><td></td><td></td></tr> <tr><td>50</td><td>151</td><td>BROWN CLAY</td><td></td><td></td><td></td></tr> <tr><td>151</td><td>160</td><td>MEDIUM SAND</td><td></td><td></td><td></td></tr> <tr><td>160</td><td>161</td><td>ROCK</td><td></td><td></td><td></td></tr> <tr><td>161</td><td>180</td><td>CALACHIE CLAY</td><td></td><td></td><td></td></tr> <tr><td>180</td><td>195</td><td>MEDIUM SAND GRAVEL</td><td></td><td></td><td></td></tr> <tr><td>195</td><td>205</td><td>CALACHIE CLAY</td><td></td><td></td><td></td></tr> <tr><td>205</td><td>225</td><td>CALACHIE CLAY SAND</td><td></td><td></td><td></td></tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	20	TOPSOIL SANDY CLAY				20	45	CALACHIE CLAY				45	50	SANDY CLAY				50	151	BROWN CLAY				151	160	MEDIUM SAND				160	161	ROCK				161	180	CALACHIE CLAY				180	195	MEDIUM SAND GRAVEL				195	205	CALACHIE CLAY				205	225	CALACHIE CLAY SAND			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																		
0	20	TOPSOIL SANDY CLAY																																																																					
20	45	CALACHIE CLAY																																																																					
45	50	SANDY CLAY																																																																					
50	151	BROWN CLAY																																																																					
151	160	MEDIUM SAND																																																																					
160	161	ROCK																																																																					
161	180	CALACHIE CLAY																																																																					
180	195	MEDIUM SAND GRAVEL																																																																					
195	205	CALACHIE CLAY																																																																					
205	225	CALACHIE CLAY SAND																																																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 11/04/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 11/21/94 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Josiah Crick</i>																																																																							

(Continued)

1 LOCATION OF WATER WELL: COUNTY: FORD		Fraction 1/4 1/4 1/4	Section Number 25	Township Number T 29 S	Range Number R 24 E									
2 WATER WELL OWNER: HELLSTORM, AL RR#, St. Address, Box #: 208 BLOOM ST. City, State, ZIP code : BLOOM, KS 67833-		Board of Agriculture, Division of Water Resources Application Number:												
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr><td>225</td><td>240</td><td>CALACHIE CLAY SAND</td></tr> <tr><td>240</td><td>0</td><td>BLUE SHALE</td></tr> </tbody> </table>		FROM	TO	LITHOLOGIC LOG	225	240	CALACHIE CLAY SAND	240	0	BLUE SHALE				
FROM	TO	LITHOLOGIC LOG												
225	240	CALACHIE CLAY SAND												
240	0	BLUE SHALE												