

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: 029 FORD	SE	1/4 SE 1/4 SE 1/4	15	T 29 S	R 26 W

Distance and direction from nearest town or city street address of well if located within city?
APPROX. 9 MILES NORTH & 3 MILES EAST OF FOWLER

2 WATER WELL OWNER:		STURGEON FARMS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT. 1, BOX 36A		Application Number: 33230,F062
City, State, ZIP code :	FOWLER, KS 67844-		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 295	ELEVATION:
		Depth(s) Groundwater Encountered	1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL	86 ft. below land surface measured on mo/day/yr 03/29/91
Pump test data: Well water was	152 ft. after 4 hours pumping 1851 gpm
Estimated Yield	1800 gpm: Well water was ft. after hours pumping gpm
Bore Hole Diameter	24 in. to 295 ft., and in. to ft.
WELL WATER TO BE USED AS: 02 IRRIGATION	
Was a chemical/bacteriological sample submitted to department? No ;	
If yes, mo/day/yr sample was submitted Water well disinfected? No	

5 TYPE OF BLANK CASING USED: 01 STEEL		CASING JOINTS: WELDED
Blank casing diameter	16 in. to 295 ft., Dia	in. to ft., Dia in. to ft.
Casing height above land surface	12 in., weight	37 lbs/ft. Wall thickness or gauge No. .219
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL		
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT		

SCREEN PERFORATED INTERVALS:	From 172 ft. to 292 ft., From ft. to ft.
	From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 295 ft., From ft. to ft.
	From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout intervals: From	ft. to 20 ft., From ft. to ft., From ft. to ft.
What is the nearest source of possible contamination: NONE OBSERVED	
Direction from well?	How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	2	01 CLAY			
2	114	04 SANDY CLAY 05 SAND			
114	160	01 CLAY			
160	169	04 SANDY CLAY			
169	200	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
200	205	04 SANDY CLAY			
205	224	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
224	263	07 FINE SAND 23 SANDSTONE 01 CLAY			
263	292	06 VERY FN SAND 07 FINE SAND			
292	298	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/26/91 and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 04/06/91
under the business name of HENKLE DRILLING & SUPPLY	by (signature) <i>Bruce J. Reichardt</i>

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 029 FORD	SE 1/4 SE 1/4 SE 1/4	15	T 29 S	R 26 W

2 WATER WELL OWNER:	STURGEON FARMS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT. 1, BOX 36A	Application Number: 33230,F062
City, State, ZIP code :	FOWLER, KS 67844-	

FROM	TO	LITHOLOGIC LOG
298	302	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/26/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/06/91 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Bruce Reichmann