

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 029 FORD NW 1/4 NW 1/4 SW 1/4 26 T 29 S R 26 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 7.5 MILES NORTH AND 3 MILES EAST OF FOWLER.

2 WATER WELL OWNER: EUGENE JONES
 RR#, St. Address, Box #: R.R. 3, BOX 294 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number: 17,164

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 266 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 84 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 84 ft. below land surface measured on mo/day/yr 04/29/92
 Pump test data: Well water was 211 ft. after 4 hours pumping 844 gpm
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 266 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 16 in. to 266 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 20 lbs/ft. Wall thickness or gauge No. .616
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 126 ft. to 266 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 266 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 58

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	8	01 CLAY			
8	34	01 CLAY			
34	48	01 CLAY			
48	58	01 CLAY			
58	60	01 CLAY			
60	75	01 CLAY			
75	80	01 CLAY			
80	95	05 SAND 13 FINE GRAVEL 01 CLAY			
95	100	01 CLAY			
100	128	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/06/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 029 FORD NW 1/4 NW 1/4 SW 1/4 26 T 29 S R 26 W

2 WATER WELL OWNER: EUGENE JONES
RR#, St. Address, Box # : R.R. 3, BOX 294

Board of Agriculture, Division of Water Resources

City, State, ZIP code : DODGE CITY, KS 67801-

Application Number: 17,164

FROM	TO	LITHOLOGIC LOG
128	134	01 CLAY 05 SAND
134	160	05 SAND 13 FINE GRAVEL 01 CLAY
160	170	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
170	190	05 SAND 13 FINE GRAVEL 01 CLAY
190	199	01 CLAY
199	205	05 SAND 13 FINE GRAVEL 01 CLAY
205	209	01 CLAY
209	219	05 SAND 11 GRAVEL
219	232	01 CLAY 20 LIMESTONE
232	240	05 SAND 11 GRAVEL 28 ROCK
240	260	01 CLAY 20 LIMESTONE
260	263	01 CLAY 23 SANDSTONE
263	285	19 SHALE
285	300	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/06/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas A. Henkle*