

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>FORD</b>	Fraction <b>SW 1/4 SW 1/4 NW 1/4</b>	Section number <b>34</b>	Township number <b>T 29 S</b>	Range number <b>R 26 E</b>	
2. Distance and direction from nearest town or city: Street address of well location if in city: <b>9N-1E-1/2S of FOWLER, KANS.</b>			3. Owner of well: <b>MILLS ESTATE</b> R.R. or street: <b>1/2 FOWLER STATE BANK</b> City, state, zip code: <b>FOWLER, KANS.</b>				
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. <b>28</b> in. Completion date <b>MARCH 3, 1976</b> Well depth <b>255</b> ft.			
5. Type and color of material		From		To		7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
TOP SOIL		0		3		8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other <input type="checkbox"/>	
CLAY		3		35		9. Casing: Material <b>STEEL</b> Height: <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia <b>16</b> in. to <b>255</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth <b>188</b>	
SAND - (FINE)		35		80		10. Screen: Manufacturer's name <b>DOZER METAL PRODUCTS</b> Type <b>PUNCH PERF</b> Dia. <b>16</b> in. Slot gauge <b>3/16</b> Length <b>20</b> ft. Set between <b>175</b> ft. and <b>255</b> ft. Gravel pack? <b>YES</b> Size range of material <b>1/4 X 3/8</b>	
CLAY		80		110		11. Static water level: <input type="checkbox"/> mo./day/yr. <b>35</b> ft. below land surface Date <b>MARCH 4, 76</b>	
SAND (FINE - COARSE) (Good)		110		180		12. Pumping level below land surfaces: <b>240</b> ft. after <b>2</b> hrs. pumping <b>1200</b> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>1200</b> g.p.m.	
CLAY		180		210		13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
SAND + GRAVEL (COARSE - VERY GOOD)		210		250		14. Well head completion: Pitless adapter <b>12</b> inches above grade	
Shale		250		255		15. Well grouted? <b>YES</b> With: Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete <input type="checkbox"/> Depth: From <b>0</b> ft. to <b>10</b> ft.	
						16. Nearest source of possible contamination: <b>NONE</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
						17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>FAIRBANKS MORSE</b> Model number <b>7000</b> HP <b>100</b> Volts <input type="checkbox"/> Length of drop pipe <b>240</b> ft. capacity <b>1000</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other <input type="checkbox"/>	
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>BRAU DRILLING CO. 217</b> Business name <b>BUCKLIN, KANS.</b> License No. <input type="checkbox"/> Address <b>BUCKLIN, KANS.</b> Signed <b>RUBEN</b> Date <b>MARCH 9, 76</b> Authorized representative			