

SWSW NW


1 Location of well:	County <u>Ford</u>	Township name <u>Wilburn</u>	Fraction <u>34</u>	Section number <u>34</u>	Town number <u>29S</u>	Range number <u>26W</u>
---------------------	--------------------	------------------------------	-------------------------------	-------------------------------------	-----------------------------------	------------------------------------

Distance and direction from nearest town or city: 9N, 1E, 1/2 S, of
Street address of well location if in city: Fowler

3 Owner of well: Miller Est.
Address: Flower STATE BANK, Fowler, KS

Locate with "X" in section below:

Sketch map:



Flower KANSAS 9 miles
North 1 Mile East 1/2 South

4 Well depth: <u>255</u> ft. Date of completion <u>7-15-75</u> Well diameter <u>28</u> in.
5 <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
6 Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Commercial <input type="checkbox"/> Test well
7 Casing: Material <u>STEEL</u> Height: above/below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. Diam. <u>16</u> in. to <u>255</u> ft. depth Drive shoe? <input type="checkbox"/> Yes <input type="checkbox"/> No <u>16</u> in. to <u>255</u> ft. depth

2	Type and color of material	From	To
	<u>TOP SOIL</u>	<u>0</u>	<u>3</u>
	<u>CLAY</u>	<u>3</u>	<u>35</u>
	<u>SAND</u>	<u>35</u>	<u>80</u>
	<u>CLAY</u>	<u>80</u>	<u>110</u>
	<u>SAND</u>	<u>110</u>	<u>180</u>
	<u>CLAY</u>	<u>180</u>	<u>215</u>
	<u>SAND & GRAVEL</u>	<u>215</u>	<u>250</u>
	<u>SHALE</u>	<u>255</u>	

8 Screen:
Manufacturer <u>DOERR</u>
Type <u>PUNCI</u> Dia. <u>16</u>
Slot gauge <u>3/16</u> Length <u>60</u>
Set between <u>195</u> ft. and <u>255</u> ft.
Fittings:
Gravel pack <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Size range of material <u>1/4 to 1/8</u>

9 Static water level:
<u>35</u> ft. below land surface Date <u>7-15-75</u>
10 Pumping level below land surfaces:
<u>240</u> ft. after <u>2</u> hrs. pumping <u>1000</u> g.p.m.
<u>240</u> ft. after <u>7 DAYS</u> pumping <u>600</u> g.p.m.
Estimated maximum yield <u>600</u> g.p.m.

11 Water sample submitted:
<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____

12 Well head completion:
<input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade

13 Well grouted? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
<input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> <u>CLAY/SLT</u>
Depth: From <u>10</u> ft. to <u>2</u> ft. <u>GROUND LEVEL</u>

14 Nearest source of possible contamination: <u>NONE</u>
ft. _____ Direction _____ Type _____
Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

15 Pump: <u>1</u>
<input type="checkbox"/> Not installed
Manufacturer's name <u>FAR, BARKS, MORIS</u>
Model number <u>1000</u> HP <u>100</u> Volts _____
Length of drop pipe <u>240</u> ft. capacity <u>600</u> g.p.m.
Type:
<input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine
<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating
<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other

16 Remarks: elevation
<u>FIAT WE COMPLETE THIS WELL IN JULY</u>
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley
<u>BUT WE DO NOT HAVE IT TO PRODUCTION</u>
<u>YET WE ARE STILL WORKING ON IT & IT</u>
<u>IS NOT PAID FOR YET</u>

17 Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
<u>BAU DRILLING CO. SON 217</u>
Business name _____ License No. _____
Address <u>21556 BUCKLEY</u>
Signed <u>Robert W. Brown</u> Date _____
Authorized representative

29 26W 34 SWSW NW