

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL:	<input type="checkbox"/> Fraction	<input type="checkbox"/> Section Number	<input type="checkbox"/> Township Number	<input type="checkbox"/> Range Number
COUNTY: 035 GRAY	<input type="checkbox"/> NE 1/4 NW 1/4 NE 1/4	<input type="checkbox"/> 36	<input type="checkbox"/> T 29 S	<input type="checkbox"/> R 27 W

Distance and direction from nearest town or city street address of well if located within city?  
APPROX. 7 MILES NORTH AND 1 1/2 MILES WEST OF FOWLER

12 WATER WELL OWNER:	BOB SOBBA	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	R.R. 1, BOX 32	Application Number: 1442
City, State, ZIP code :	FOWLER, KS 67844-	

13 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	<input checked="" type="checkbox"/>	4 DEPTH OF COMPLETED WELL 255 ELEVATION: Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
<input type="checkbox"/> NW <input type="checkbox"/> NE		WELL'S STATIC WATER LEVEL 120 ft. below land surface measured on mo/day/yr 03/23/91 Pump testdata: Well water was 170 ft. after 4 hours pumping 1204 gpm
<input type="checkbox"/> S <input type="checkbox"/> E		Estimated Yield 1200 gpm: Well water was ft. after hours pumping gpm
<input type="checkbox"/> W <input type="checkbox"/> E		Bore Hole Diameter 30 in. to 255 ft., and in. to ft.
<input type="checkbox"/> E <input type="checkbox"/> W		WELL WATER TO BE USED AS: 02 IRRIGATION
<input type="checkbox"/> SW <input type="checkbox"/> SE		Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? No

14 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter 16 in. to 255 ft., Dia in. to ft., Dia in. to ft.	
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	

SCREEN PERFORATED INTERVALS:	From 157 ft. to 247 ft., From ft. to ft.
GRAVEL PACK INTERVALS:	From ft. to ft., From ft. to ft.
From 20 ft. to 257 ft., From ft. to ft.	
From ft. to ft., From ft. to ft.	

15 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From ft. to 20 ft., From ft. to ft., From ft. to ft.	
What is the nearest source of possible contamination: 14 ABAND. WELL	
Direction from well? WEST	How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
2	2	01 CLAY			
2	44	04 SANDY CLAY 01 CLAY 20 LIMESTONE			
44	77	07 FINE SAND 08 MEDIUM SAND			
77	93	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
93	97	04 SANDY CLAY			
97	129	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
129	151	04 SANDY CLAY			
151	170	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
170	171	01 CLAY			
171	193	13 FINE GRAVEL 14 MED GRAVEL			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/19/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/06/91 under the business name of HENKLE DRILLING & SUPPLY	by (signature) <i>Bruce Luehrmann</i>
---	---------------------------------------

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction			1 Section Number	1 Township Number	1 Range Number
1 COUNTY: 035 GRAY	1 NE	1/4 NW	1/4 NE	1/4	1 36	1 T 29 S R 27 W

12 WATER WELL OWNER:	BOB SOBBA	Board of Agriculture, Division of Water Resources
1 RR#, St. Address, Box # :	R.R. 1, BOX 32	Application Number: 1442
1 City, State, ZIP code :	FOWLER, KS 67844-	

FROM TO LITHOLOGIC LOG

193	197	01 CLAY 20 LIMESTONE
197	210	07 FINE SAND 08 MEDIUM SAND 01 CLAY
210	212	01 CLAY
212	229	07 FINE SAND 20 LIMESTONE
229	236	01 CLAY
236	247	07 FINE SAND 28 ROCK
247	253	19 SHALE
253	262	19 SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/19/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/06/91 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Benny Leichtmuth*