

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GREY	NW 1/4 SE 1/4 SE 1/4	36	T 29 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?

7 N. OF FOWLER, KS.

2 WATER WELL OWNER:	DANA REESE FRAZIER 426	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	10213 YUCCA RD	

City, State, ZIP code :	FOWLER, KS 67844-	Application Number:
-------------------------	-------------------	---------------------

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 198 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 88 ft. 2. 0 ft. 3. 0 ft.

/ \					WELL'S STATIC WATER LEVEL 88 ft. below land surface measured on mo/day/yr Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
1	--- NW ---	NE			Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
M					
i	W	---	E		Bore Hole Diameter 8.75 in. to 198 ft., and in. to 0 ft.
1					
e					WELL WATER TO BE USED AS: 01 DOMESTIC
	--- SW ---	SE			Was a chemical/bacteriological sample submitted to department? No ;
/ \					If yes, mo/day/yr sample was submitted Water well disinfected? Yes;
---	---	---	---	---	

5 TYPE OF BLANK CASING USED: 02 PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 178 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 21-26	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT	

SCREEN PERFORATED INTERVALS:	From 178 ft. to 198 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 198 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From 1 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: CATTLE PASTURE	
Direction from well? ALL	How many feet? 4

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	15	BROWN CLAY			
15	32	17 GRAVEL			
32	62	TAN CLAY			
62	73	GREY CLAY			
73	76	BROWN 05 SAND			
76	81	CHERTY			
81	129	05 SAND			
129	197	17 GRAVEL			
197	198	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 9/10/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 09/12/98 under the business name of CARL HAYSE WATER WELL SVC by (signature) <i>Carl Hayse</i>
---