

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number												
COUNTY: GRAY		NW 1/4 NW 1/4 NW 1/4	19	T 29 S	R 28 W												
Distance and direction from nearest town or city street address of well if located within city? FROM MONTEZUMA - EAST EDGE 5 3/4 MILES SOUTH																	
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources															
RR#, St. Address, Box #: 33006 13 ROAD		Application Number:															
City, State, ZIP code: MONTEZUMA, KS 67867-																	
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 390 ELEVATION: 2252 PM															
<table border="1"> <tr> <td>X</td> <td></td> <td></td> <td></td> </tr> <tr> <td>NW</td> <td></td> <td>NE</td> <td></td> </tr> <tr> <td>SW</td> <td></td> <td>SE</td> <td></td> </tr> </table>		X				NW		NE		SW		SE		Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 140 ft. below land surface measured on mo/day/yr 06/03/96 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 75 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 390 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No; If yes, mo/day/yr sample was submitted Water well disinfected? Yes			
X																	
NW		NE															
SW		SE															
5 TYPE OF BLANK CASING USED: PVC		CASING JOINTS: GLUED															
Blank casing diameter 5 in. to 390 ft., Dia in. to 0 ft., Dia in. to 0 ft.																	
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17																	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC																	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT																	
SCREEN PERFORATED INTERVALS:		From 305 ft. to 385 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 30 ft. to 390 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.															
6 GROUT MATERIAL BENTONITE																	
Grout intervals: From 0 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.																	
What is the nearest source of possible contamination: ABANDONED WELL																	
Direction from well? NORTH		How many feet? 25															
FROM TO LITHOLOGIC LOG		FROM TO		PLUGGING INTERVALS													
0	20																
20	40																
40	75																
75	100																
100	150																
150	180																
180	200																
200	220																
220	260																
260	280																
LITHOLOGIC LOG																	
TOPSOIL CLAY																	
CLAY																	
CLAY FINE SAND CALACHIE																	
FINE - MED SAND																	
FINE - MED SAND SMALL GRAVEL																	
CLAY THIN ROCK LAYER FINE SAND																	
CLAY THIN ROCK LAYER																	
CLAY ROCK LAYERS																	
GRAY CLAY ROCK LAYERS																	
GRAY CLAY																	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/06/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 06/18/96 under the business name of JOE'S WELL SERVICE, INC. by signature <i>Judith Creek</i>																	

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY		NW 1/4 NW 1/4 NW 1/4	19	T 29 S	R 28 W
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: 33006 13 ROAD		Application Number:			
City, State, ZIP code: MONTEZUMA, KS 67867-					
FROM TO LITHOLOGIC LOG					
280	300	GRAY CLAY SANDSTONE LAYER(S)			
300	400	SANDSTONE			