

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 SE 1/4 Section Number 18 Township Number T 29 S Range Number R 28 W
COUNTY: GRAY

Distance and direction from nearest town or city street address of well if located within city?
FROM MONTE - 4 MILES SOUTH, 1 MILE EAST AND 1/2 MILE SOUTH

2 WATER WELL OWNER: THOMAS, VIC
RE#, St. Address, Box #: BOX 381
City, State, ZIP code : MONTEZUMA, KS 67867- Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:
4 DEPTH OF COMPLETED WELL 345 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
WELL'S STATIC WATER LEVEL 144 ft. below land surface measured on mo/day/yr
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 8 in. to 345 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 345 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 300 ft. to 340 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 20 ft. to 345 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE - NEW SITE
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	TOPSOIL BROWN CLAY			
10	40	SANDY CLAY			
40	42	FINE SAND			
42	50	SAND CLAY			
50	57	FINE SAND			
57	84	MEDIUM SAND SMALL GRAVEL			
84	90	SAND CLAY			
90	95	ROCK CLAY			
95	118	CLAY ROCK LAYER(S)			
118	125	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/03/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 12/21/93 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judie Clark*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 SE 1/4 Section Number 18 Township Number T 29 S Range Number R 28 W
COUNTY: GRAY

2 WATER WELL OWNER: THOMAS, VIC
RE#, St. Address, Box #: BOX 381
City, State, ZIP code : MONTEZUMA, KS 67867- Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG		
125	140	BLUE SHALE		
140	193	GRAY SHALE		
193	241	BLUE SHALE ROCK LAYERS		
241	242	ROCK		
242	270	BLUE SHALE		
270	271	ROCK		
271	280	GRAY SHALE		
280	340	SANDSTONE GRAY SHALE		
340	360	GRAY SHALE		