


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | | |
|---|---|---|---|---------------------------|---|---|
| 1. Location of well: | County | Fraction <i>5/8 SE 1/4 SW 1/4 SE 1/4</i> | Section number 35 | Township number T 29 S | Range number R 30 E | |
| 2. Distance and direction from nearest town or city: Copeland, Kansas. Street address or well location if in city: | 3. Owner of well: Frank Stude R.R. or street: City, state, zip code: Sublette, Kansas | | | | | |
| 4. Locate with "X" in section below:  | | | Sketch map: 2000' W of SE corner of SE 1/4, Sec. 35, T29S, R39W, Gray County, Kansas. | | | |
| 5. Type and color of material | | | From | To | 6. Bore hole dia. 28 in. Completion date 10/27/76 Well depth 450 ft. | |
| Top soil | | | 0 | 3 | 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary | |
| Tan clay | | | 3 | 74 | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | |
| Coarse sand with clay streaks | | | 74 | 124 | 9. Casing: Material stl Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 37 lbs./ft. Dia 16 in. to 162 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 219 | |
| Tan clay | | | 124 | 128 | 10. Screen: Manufacturer's name Foster, Doerr Type milslot, lower 16" Slot/gauze 1/8" Length 288' Set between 162 ft. and 450 ft. ft. and <input type="checkbox"/> ft. Gravel pack? yes Size range of material 3.5mm | |
| Coarse sand | | | 128 | 200 | 11. Static water level: mo./day/yr. 157 ft. below land surface Date 8/6/76 | |
| Coarse sand | | | 200 | 300 | 12. Pumping level below land surfaces: 180 ft. after 1/2 hrs. pumping 1500 g.p.m. 191 ft. after 1 hrs. pumping 2520 g.p.m. Estimated maximum yield 2600 g.p.m. | |
| Coarse sand | | | 300 | 314 | 13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/> | |
| Tan clay | | | 314 | 420 | 14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade | |
| Coarse sand with fine to coarse gravel | | | 420 | 438 | 15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft. | |
| Tan clay | | | 438 | 450 | 16. Nearest source of possible contamination: unk. ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | |
| (Use a second sheet if needed) | | | | | 17. Pump: Not installed Manufacturer's name Layne & Bowler Model number 14 TL HP 150 Volts Length of drop pipe 260 ft. capacity 2000 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | |
| 18. Elevation: | 19. Remarks: | | | | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne-Western Co., Inc. 102 Business name Garden City, Kansas License No. Address Garden City, Kansas Signed <i>R. L. Vincent</i> Date 18 Nov 76 Authorized representative 18 Nov 76 |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | | |