

WATER WELL RECORD FORM WWC-5 KSA 82A-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	FRACTION SW 1/4 SW 1/4 NW 1/4	SECTION NUMBER 17	TOWNSHIP NUMBER T 29 S	RANGE NUMBER R 30 W
---	----------------------------------	----------------------	---------------------------	------------------------

DISTANCE AND DIRECTION FROM NEAREST TOWN OR CITY STREET ADDRESS OF WELL IF LOCATED WITHIN CITY?
FROM COPELAND; APPX 1 MILE SOUTH

2 WATER WELL OWNER: CITY OF COPELAND
RR#, ST. ADDRESS, Box #: PO BOX 219

BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES

CITY, STATE, ZIP CODE : COPELAND, KS 67838-0219

APPLICATION NUMBER: Gray Co #3

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 403 ELEVATION: 0 DEPTH(S) GROUNDWATER ENCOUNTERED 1. 0 FT. 2. 0 FT. 3. 0 FT.
1 NW NE M X E L SW SE E	WELL'S STATIC WATER LEVEL 243 FT. BELOW LAND SURFACE MEASURED ON MO/DAY/YR 06/11/02 PUMP TESTDATA: WELL WATER WAS 250 FT. AFTER 8 HOURS PUMPING 375 GPM ESTIMATED YIELD 0 GPM; WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM BORE HOLE DIAMETER 36 IN. TO 403 FT., AND IN. TO 0 FT. WELL WATER TO BE USED AS: 05 PUB. WTR SUP WAS A CHEMICAL/BACTERIOLOGICAL SAMPLE SUBMITTED TO DEPARTMENT? NO; IF YES, MO/DAY/YR SAMPLE WAS SUBMITTED WATER WELL DISINFECTED? YES

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

BLANK CASING DIAMETER 12.75 IN. TO 403 FT., DIA IN. TO 0 FT., DIA IN. TO 0 FT.

CASING HEIGHT ABOVE LAND SURFACE 36 IN., WEIGHT 50 LBS/FT. WALL THICKNESS OR GAUGE NO. .375

TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	FROM 310 FT. TO 380 FT., FROM 0 FT. TO 0 FT.
	FROM 388 FT. TO 398 FT., FROM 0 FT. TO 0 FT.
GRAVEL PACK INTERVALS:	FROM 50 FT. TO 403 FT., FROM 0 FT. TO 0 FT.
	FROM 0 FT. TO 0 FT., FROM 0 FT. TO 0 FT.

6 GROUT MATERIAL 02 CEMENT GROUT 03 BENTONITE

GROUT INTERVALS: FROM 0 FT. TO 50 FT., FROM 250 FT. TO 255 FT., FROM 0 FT. TO 0 FT.

WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION: NONE OBSERVED

DIRECTION FROM WELL?

HOW MANY FEET?

0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	40	04 SANDY CLAY 31 CALICHE 01 CLAY			
40	49	01 CLAY			
49	58	05 SAND 01 CLAY			
58	103	05 SAND 11 GRAVEL 01 CLAY			
103	108	05 SAND 11 GRAVEL 04 SANDY CLAY			
108	116	05 SAND 11 GRAVEL 01 CLAY			
116	139	05 SAND 13 FINE GRAVEL 01 CLAY			
139	151	05 SAND 11 GRAVEL 01 CLAY			
151	255	05 SAND 11 GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS COMPLETED ON (MO/DAY/YEAR) 06/07/02 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF. KANSAS WATER WELL CONTRACTOR'S LICENSE NO. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 06/21/02 UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE)

(CONTINUED)

WATER WELL RECORD FORM WWC-5 KSA 82A-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	FRACTION SW 1/4 SW 1/4 NW 1/4	SECTION NUMBER 17	TOWNSHIP NUMBER T 29 S	RANGE NUMBER R 30 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: CITY OF COPELAND
RR#, ST. ADDRESS, Box #: PO BOX 219

BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES

CITY, STATE, ZIP CODE : COPELAND, KS 67838-0219

APPLICATION NUMBER:

FROM	TO	LITHOLOGIC LOG
255	263	05 SAND 11 GRAVEL
263	283	05 SAND 11 GRAVEL 01 CLAY
283	292	05 SAND 11 GRAVEL
292	308	05 SAND 11 GRAVEL
308	323	05 SAND 11 GRAVEL 01 CLAY
323	363	05 SAND 11 GRAVEL 01 CLAY
363	380	05 SAND 11 GRAVEL 01 CLAY
380	387	04 SANDY CLAY 20 LIMESTONE 01 CLAY
387	398	05 SAND 13 FINE GRAVEL 01 CLAY
398	455	04 SANDY CLAY 20 LIMESTONE 05 SAND
455	477	04 SANDY CLAY 05 SAND 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS
COMPLETED ON (MO/DAY/YEAR) 06/07/02 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF. KANSAS
WATER WELL CONTRACTOR'S LICENSE NO. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 06/21/02
UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE) *Donny Henkelle*