

## WATER WELL RECORD

## Form WWC-5

### Division of Water Resources; App. No.

20,886

**7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:** This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ..... **3-15-08**... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **208**..... This Water Well Record was completed on (mo/day/year) **3-20-08**..... under the business name of **Minter-Wilson Drilling Co. Inc.** by (signature) **Mark Wilson**.

under the business name of Miller-Wilson Drilling Co., Inc. (Signature) John Miller  
**INSTRUCTIONS:** Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>

*The  
Professionals*

# MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME            FRY FAMILY FARMS  
COUNTY        GRAY  
DATE            1-4-08

LOCATION        NW 1/4 14-29-30 - FROM COPELAND - 3/4 OF A MILE SOUTH,  
                  3 MILES EAST & 1/4 OF A MILE SOUTH ON  
                  THE EAST SIDE  
                  - FROM PIVOT - 117 FT. WEST

STATIC WATER LEVEL - 200 FT.

## TEST #2

0' TO 3' - TOP SOIL  
3' TO 7' - BROWN CLAY  
7' TO 45' - BROWN SANDY CLAY  
45' TO 67' - FINE TO MEDIUM SAND & GRAVEL  
67' TO 71' - BROWN SANDY CLAY  
71' TO 87' - FINE TO MEDIUM SAND & GRAVEL  
87' TO 91' - BROWN SANDY CLAY  
91' TO 113' - FINE TO MEDIUM SAND & GRAVEL  
113' TO 121' - BROWN SANDY CLAY  
121' TO 136' - BROWN SANDY CLAY WITH GRAVEL STREAKS  
136' TO 157' - FINE TO MEDIUM SAND & GRAVEL  
157' TO 189' - BROWN SANDY CLAY WITH GRAVEL STREAKS  
189' TO 222' - FINE TO MEDIUM SAND & GRAVEL  
222' TO 236' - BROWN & BLUE CLAY  
236' TO 244' - BROWN & BLUE CLAY WITH STREAKS OF GRAVEL  
244' TO 276' - FINE TO MEDIUM SAND & GRAVEL  
276' TO 282' - BROWN SANDY CLAY  
282' TO 291' - BROWN CLAY WITH STRIPS OF BROWN ROCK  
291' TO 312' - FINE TO MEDIUM SAND & GRAVEL  
312' TO 328' - BROWN CLAY WITH FINE TO MEDIUM SAND & GRAVEL 20%  
328' TO 341' - BROWN CLAY  
341' TO 352' - FINE TO MEDIUM SAND & GRAVEL  
352' TO 395' - BROWN SANDY CLAY WITH GRAVEL STREAKS 10%  
395' TO 430' - CLAY  
430' TO 435' - BROWN YELLOW CLAY  
435' TO 440' - SHALE