

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL LOT 2 1/4 NW 1/4 NE 1/4 1 T 29 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 1/2 MILES WEST AND 1 MILE NORTH OF COPELAND.

2 WATER WELL OWNER: WESTERN PACIFIC FARMS
 RR#, St. Address, Box #: RT. 1, BOX 68 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: COPELAND, KS 67837- Application Number: 4,018

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 485 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 225 ft. below land surface measured on mo/day/yr 11/24/93
 Pump testdata: Well water was 295 ft. after 4 hours pumping 1396 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 30 in. to 485 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 485 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 257 ft. to 380 ft., From 470 ft. to 480 ft.
 From 412 ft. to 442 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 485 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 280

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	43	03 SILTY CLAY 31 CALICHE 07 FINE SAND			
43	63	04 SANDY CLAY 07 FINE SAND			
63	70	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
70	80	01 CLAY 07 FINE SAND			
80	110	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
110	118	04 SANDY CLAY			
118	142	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
142	159	04 SANDY CLAY			
159	279	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
279	285	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/19/93 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/26/93
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

Board of Agriculture, Division of Water Resources
Application Number: 4,018

by (signature)