

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 SE 1/4 SW 1/4 05 T 29 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 4.25 MILES NORTH AND 5.75 MILES EAST OF SUBLETTE.

2 WATER WELL OWNER: SUBLETTE FEEDERS
 RR#, St. Address, Box #: BOX 917 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number: 40,376 - NORTH WELL OF BATTERY OF TWO

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 649 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 260 ft. below land surface measured on mo/day/yr 11/09/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17.5 in. to 649 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 8.625 in. to 649 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 22 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 330 ft. to 430 ft., From 605 ft. to 645 ft.
 From 475 ft. to 515 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 649 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: WATER WELL
 Direction from well? SOUTH How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	54	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
54	69	07 FINE SAND 08 MEDIUM SAND			
69	109	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL			
109	112	04 SANDY CLAY 07 FINE SAND			
112	161	05 SAND 14 MED GRAVEL 01 CLAY			
161	246	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL			
246	274	01 CLAY			
274	301	05 SAND 13 FINE GRAVEL			
301	310	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/09/93 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/18/93
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NE 1/4 SE 1/4 SW 1/4	05	T 29 S	R 31 W

2 WATER WELL OWNER: SUBLETTE FEEDERS

RR#, St. Address, Box #: BOX 917

Board of Agriculture, Division of Water Resources

City, State, ZIP code: SUBLETTE, KS 67877-

Application Number: 40,376 - NORTH

FROM	TO	LITHOLOGIC LOG
310	317	07 FINE SAND
317	324	01 CLAY
324	429	05 SAND 13 FINE GRAVEL 01 CLAY
429	474	04 SANDY CLAY 20 LIMESTONE
474	519	05 SAND 01 CLAY
519	533	04 SANDY CLAY
533	556	07 FINE SAND 28 ROCK
556	585	19 SHALE
585	603	19 SHALE
603	646	23 SANDSTONE 19 SHALE
646	677	19 SHALE
677	682	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/09/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/18/93 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*