

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 SW 1/4 SW 1/4 07 T 29 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 4.25 MILES EAST AND 3.25 MILES NORTH OF SUBLETTE.

2 WATER WELL OWNER: KOELLING, EVERETT

RR#, St. Address, Box #: 2006 LA MESA

Board of Agriculture, Division of Water Resources

City, State, ZIP code : DODGE CITY, KS 67801-

Application Number: 13,824

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10

4 DEPTH OF COMPLETED WELL 631 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 248 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 248 ft. below land surface measured on mo/day/yr 07/23/92
 Pump test data: Well water was 277 ft. after 4 hours pumping 1509 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 30 in. to 500 ft., and 24 in. to 631 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

Blank casing diameter 16 in. to 270 ft., Dia 20 in. to 470 ft., Dia 16 in. to 631 ft.

Casing height above land surface 12 in., weight 53 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 270 ft. to 310 ft., From 343 ft. to 353 ft.

From 311 ft. to 331 ft., From 371 ft. to 381 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 631 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHEAST

How many feet? 2035

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	60	04 SANDY CLAY 31 CALICHE 07 FINE SAND			
60	100	07 FINE SAND 08 MEDIUM SAND 11 GRAVEL			
100	107	04 SANDY CLAY			
107	331	05 SAND 35 CLAY & GRAVEL			
331	343	04 SANDY CLAY 20 LIMESTONE 05 SAND			
343	353	05 SAND 11 GRAVEL			
353	372	04 SANDY CLAY 20 LIMESTONE 05 SAND			
372	380	05 SAND 13 FINE GRAVEL			
380	398	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/15/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/08/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Donna B. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NW 1/4 SW 1/4 SW 1/4 07 T 29 S R 31 W

2 WATER WELL OWNER: KOELLING, EVERETT

RR#, St. Address, Box #: 2006 LA MESA

Board of Agriculture, Division of Water Resources

City, State, ZIP code : DODGE CITY, KS 67801-

Application Number: 13,824

SCREEN PERFORATED INTERVALS: From 399 ft. to 409 ft., From 472 ft. to 482 ft.
 From 425 ft. to 435 ft., From 515 ft. to 525 ft.

FROM	TO	LITHOLOGIC LOG
398	410	07 FINE SAND 20 LIMESTONE 04 SANDY CLAY
410	423	04 SANDY CLAY
423	436	07 FINE SAND 04 SANDY CLAY 20 LIMESTONE
436	447	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
447	472	01 CLAY
472	482	07 FINE SAND 08 MEDIUM SAND
482	516	01 CLAY 06 VERY FN SAND 07 FINE SAND
516	525	28 ROCK
525	534	19 SHALE 20 LIMESTONE 01 CLAY
534	585	19 SHALE 20 LIMESTONE 23 SANDSTONE
585	628	23 SANDSTONE 19 SHALE
628	648	19 SHALE 23 SANDSTONE
648	652	20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/15/92 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 10/08/92

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Douglas B. Henkle